


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Harper County, Sec. 18 Twp. 32 Rge. 8W (E) W (W)  
Location as "NE/CNW&SW" or footage from lines NE NE SW  
Lease Owner Mull Drilling Co. Inc.  
Lease Name E. Morse Well No. 1  
Office Address 670 N. 4th. Natl. Bank Bldg. Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole.  
Date well completed 11-26 19 60  
Application for plugging filed 11-26 19 60  
Application for plugging approved 11-26 19 60  
Plugging commenced 8:00 A.M. 11-26 19 60  
Plugging completed 10" A.M. 11-26 19 60  
Reason for abandonment of well or producing formation \_\_\_\_\_  
No production  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Fred Hampel  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4792 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole filled with drilling mud to depth of 4597'. Plug out at this depth with 1/2 sack hulls on top of plug, with 15 sacks cement mixed on top of plug. Hole then filled to within 35' of top of hole and 1/2 sack hulls and plug put at this depth, 10 sacks cement mixed on top of hulls completing plugging of hole. Rat hole bridged and 2 sacks cement put on top of bridge. This completed plugging.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 2 1960  
12-2-60  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Co. tools.  
Address Same as above.


STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Joseph O. Butts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joseph O. Butts  
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 28th day of November, 19 60

My commission expires January 28, 1961

Ethel Zimmerman  
Notary Public.



ROTARY DRILLERS LOG

COMPANY: Mull Drilling Co., Inc. Et Al  
Wichita, Kansas

ROTARY DRILLING COMMENCED: 11-11-60

CONTRACTOR: Mull Drilling Co., Inc.  
Wichita, Kansas

ROTARY DRILLING COMPLETED: 11-26-60

CASING RECORD: Set 200' of 8 5/8" csg.  
w/150 sax cmt.  
D & A

LOCATION: MORSE #1  
NE NE SW 18-32S-8W  
Harper County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Bushing.)

670'	Red Bed	4608'	Lime & Chert
1289'	Sand & Shale	4646'	Lime & Shale
1325'	Shale	4738'	Kinderhook
1610'	Lime & Shale	4786'	Viola
1765'	Lime	4790'	Simpson - total depth
1895'	Lime w/Shale		
1990'	Lime		
3156'	Lime w/Shale		
3430'	Sandy Lime & Shale		
3490'	Lime w/Shale		
3705'	Sandy Lime w/Shale		
3860'	Sandy Lime		
3967'	Sandy Lime & Shale		
4109'	Lime		
4398'	Lime w/Shale		
4577'	Mississippi		

RECEIVED  
STATE CONSERVATION COMMISSION

DEC 2 1960

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

MULL DRILLING COMPANY, INC.

*Robert G. Reinke*

Robert G. Reinke, Geologist

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 30th day of November, 1960



*Madge N. Miller*  
Madge N. Miller, Notary Public