


WELL PLUGGING RECORD

Give All Information Completely  
in the Required Affidavit  
and Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barber County. Sec. 21 Twp. 31 Rge. 13 (X) (W)  
Location as "NE/CNW/SE/SW" or footage from lines C SW NE  
Lease Owner Rock Island Oil & Refining  
Lease Name Smith Well No. 1  
Office Address 321 West Douglas, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5-3-64 19  
Application for plugging filed 5-3-64 19  
Application for plugging approved 5-3-64 19  
Plugging commenced 5-3-64 19  
Plugging completed 5-3-64 19  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4673 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	293' K.B.	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used  
in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

Heavy Mud to 250' Plug 1/2 sk. hulls 25 sacks cement  
Heavy Mud to 40' Plug 1/2 sk. hulls 10 sk. cement to cellar bottom  
2 sacks in rathole.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 11 1964 5.11.64

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.  
Address Box 486, Great Bend, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Leslie Kite

(employee of owner) or (owner or operator) of the above-described  
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the  
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite  
Box 486, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of May, 1964.

My commission expires April 1, 1967

Ulanda Nichols  
Notary Public.

DRILLER'S LOG

COMPANY: Rock Island Oil & Refining  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: SMITH #1  
 LOCATION: C SW NE Sec. 21-31-13  
 BARBER COUNTY, KANSAS  
 COMMENCED: 4-20-64  
 COMPLETED: 5-3-64

0	40	Redbed & Surface Clay
40	271	Redbed
271	560	Redbed & Shale
560	1131	Shale, Sand, Salt
1131	1750	Redbed & Gypsum
1750	1880	Lime & Shale
1880	2070	Shale & Lime
2070	2190	Lime
2190	2800	Lime & Shale
2800	3520	Shale & Lime
3520	3605	Lime & Shale
3605	3792	Shale & Sand
3792	4410	Lime
4410	4450	Lime & Shale
4450	4486	Lime & Chert
4486	4669	Lime
4669	4673	Simpson Sand
	<u>4673</u>	<u>Rotary Total Depth - D. &amp; A.</u>

Set 8 5/8" new surface casing @ 293' K.B. with landing joint cemented with 225 sacks Sunset

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the Smith #1 log, well located C SW NE of Section 21, Township 31, Range 13, Barber County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite  
 Leslie Kite

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 6th day of May, 1964.

Ulanda Nichols  
 Ulanda Nichols

My Commission Expires  
 April 1, 1967

RECEIVED  
 STATE CORPORATION COMMISSION

MAY 11 1964

CONSERVATION DIVISION  
 Wichita, Kansas