


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Barber County, Sec. 27 Twp. 31S Rge. 13W ~~X2~~ (W)  
Location as "NE/CNW/SW" or footage from lines C NE SW  
Lease Owner TILCO, Inc.  
Lease Name Smith Well No. 1  
Office Address Box 486, Great Bend, Kansas 67530  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 3-5-68 19  
Application for plugging filed 3-5-68 19  
Application for plugging approved 3-5-68 19  
Plugging commenced 3-5-68 19  
Plugging completed 3-5-68 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3778 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	320'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with mud to 275', bridged hole @ 275' - 25.sks. Cement Mud to 40', bridged hole @ 40' - 10 sks. cement, 2 sks. in rathole

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 8 - 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.  
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.

\_\_\_\_\_(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lueli Kite

Box 486, Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of March, 1968

My commission expires April 1, 1971

Ulanda Nichols  
Notary Public.

DRILLER'S LOG

COMPANY: TILCO, Inc.  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: SMITH #1  
 LOCATION: C NE SW SECTION 27-31S-13W  
 BARBER COUNTY, KANSAS  
 COMMENCED: 2-28-68  
 COMPLETED: 3-5-68

-----		
0	30	Surface clay
30	75	Sand
75	275	Redbed
275	998	Redbed
998	1470	Shale
1470	3460	Shale, Lime
3460	3585	Lime, Shale
3585	3715	Shale
3715	3778	Lime
	<u>3778</u>	<u>RTD - D. &amp; A.</u>

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAR 8 - 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

-----  
 8 5/8" 28# used surface casing set @ 320' cemented with 275 sacks  
 Common, 2% cc  
 -----

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Smith #1 Well, located Center Northeast Southwest (C NE SW) of Section 27, Township 31 South, Range 13 West, Barber County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite  
 Leslie Kite

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON )

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 7th day of March, 1968.

Ulanda Nichols  
 Ulanda Nichols

My Commission Expires:  
 April 1, 1971