


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Barber County. Sec. 30 Twp. 31 Rge. (E) 13 (W)  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NW NW NE  
Lease Owner Barbara Oil Company  
Lease Name Harriet Mills Well No. 1  
Office Address 322 Central Building, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 20, 1952 19  
Application for plugging filed May 20, 1952 19  
Application for plugging approved May 21, 1952 19  
Plugging commenced May 20, 1952 19  
Plugging completed May 20, 1952 19  
Reason for abandonment of well or producing formation D&A

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M.A. River, Box 148, Pratt, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4665 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				12 $\frac{1}{2}$ "	200'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 200' - pushed plug to 200' - cemented with 25 sacks cement.  
Filled with mud to 20' from bottom of cellar and cemented with 25 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 2 - 1952 6.2.52

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R.C. Patton Co.  
Address Orpheum Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
R.F. Ramsey (employee of owner) or (owner of property) of the above-described well,


being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R.F. Ramsey  
Landman  
322 Central Building, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of May, 1952.

Notary Public

My commission expires March 2, 1953



Barbara Oil Company  
Harriet Mills Well # 1  
Total Depth  
Comm.  
Comp.  
Contractor R. C. Patton Co.,

4665 Feet  
4/24/52  
5/20/52

Location  
NW NW NE Section 30-T31S-R13W  
Barber County, Kansas.  
CASING RECORD  
12 1/2" Casing at 200 Feet.  
Cemented with 275 Sacks Cement

Surface Soil	25
Sand	32
Red Shale & Shells	200
Red Shale	221
Shale & Shells	1250
Shale & Salt	1335
Shale	1360
Shale & Shells	1600
Anhydrite & Shale	1825
Shale & Lime	3731
Sand	3745
Shale & Lime	3970
Lime	4139
Shale & Lime	4173
Lime	4195
Shale & Lime	4262
Shale	4274
Shale & Lime	4297
Shale 4328	4328
Chert	4345
Chert & Lime	4361
Lime	4396
Shale & Lime	4445
Chert & Lime	4541
Shale & Lime	4575
Shale & Sand	4625
Sandy Shale	4637
Lime	4665
Total Depth	4665

STATE OF Kansas COUNTY OF Sedgwick ss,

I, the undersigned, being duly sworn, on oath state that the above statement and log is a true and correct record and log of the well drilled at the location above described.

R. C. PATTON CO.,

By R. C. Patton

Subscribed and sworn to before me this 28th day of May, 1952

J. P. Hendrick  
Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION  
1952

My Commission expires Oct 4th

JUN 2 - 1952

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 30T-21R/10  
BOOK PAGE 17 LINE 20