

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-22,208-00-00

LEASE NAME Mills Feed

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 30-1

4950 Ft. from S Section Line

4950 Ft. from E Section Line

LEASE OPERATOR Plano Petroleum Corporation

SEC. 30 TWP. 31S RGE. 13 ~~K&X&X~~(W)

ADDRESS P. O. Box 860247, Plano, TX 75086

COUNTY Barber

PHONE#(214) 422-4995 OPERATORS LICENSE NO. 5237

Plugging Completed 10-15-88

Character of Well good

Plugging Commenced 10-16-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-16-88

The plugging proposal was approved on 10-16-88 (date)

by State Plugger, Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3808'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	322.75'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Circulate heavy mud. 1st plug from 660' to 460' w/50 sx. 2nd plug from 350' to 190' w/40 sx. 3rd plug from 40' to surface w/10 sx. Rathole-15 sx. Mousehole-10 sx. All cement 60/40 posmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 801 Union Center, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Plano Petroleum Corporation

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 801 Union Center

Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 27th day of October, 19 88

Sherrie L. Brooks

Notary Public Sherrie L. Brooks

My Commission Expires: August 21, 1990.