

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barber County, Sec. 31 Twp. 31 Rge. 13 (X) (W)

Location as "NE/CNW/SW" or footage from lines NW NW SW  
Lease Owner Aylward Drilling Company  
Lease Name Young Well No. 1  
Office Address 813 1st Natl. Bank Bldg., - Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 13 1955  
Application for plugging filed December 13 1955  
Application for plugging approved December 13 1955  
Plugging commenced December 13 1955  
Plugging completed December 13 1955  
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives - Pratt, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4745 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	140'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from total depth to 135'; cement plug to 95' with 20 sacks of cement; filled with heavy mud to 35'; cement to top of surface with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Aylward Drilling Company  
Address 813 1st Natl. Bank Bldg. - Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Paul W. Hesse (employee of owner) or (Notary Public) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul W. Hesse  
813 1st Natl. Bank Bldg. - Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of December, 1955

My commission expires December 11, 1957

Duane Jessup  
DUANE JESSUP Notary Public.

PLUGGING  
FILE SEC. 31 T. 31 R. 13 W  
BOOK PAGE 24 LINE 11

RECEIVED  
STATE CORPORATION COMMISSION  
2 20 55 12-20-55

YOUNG #1

Company: Aylward Drilling Company  
 Contractor: Aylward Drilling Company

Casing Record:  
 8 5/8" - 140' w/125 sx

Commenced: November 26, 1955  
 Completed: December 13, 1955

Location:  
 NW NW SW Sec. 31-31-13W  
 Barber County, Kansas  
 Elev. 1606 R.B.

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Red bed	0	30	DST #1 - 3750' (-2147) - 3772 (-2169) open 1 1/2 hr., Rec. 580' salt water, FP 60-340#, BHP 1480#/30 min., HP 2030#/10.1# mud, Temp. 126 deg.
Sand	30	70	
Red bed, lime, shells	70	140	DST #2 - 4725 (-3122) - 4745 (-3142) Open 1 1/2 hr., strong blow, Rec. 1930' sulphur water, FP 80-950#, BHP 1670# in 30 min.
Red bed	140	575	
Anhydrite	575	590	
Shale & shells	590	1260	
Salt	1260	1340	
Shale, shells, lime strks	1340	1555	
Shale, shells	1555	1650	
Lime	1650	1745	
Lime & Shale	1745	1885	
Lime & shale streaks	1885	2020	
Hard lime	2020	2110	
Lime & shale	2110	2230	
Lime	2230	2325	
Lime & shale	2325	3755	
Shale & sand	3755	3781	
Sand & lime	3781	3820	
Lime	3820	3903	
Lime & shale	3903	4055	
Lime	4055	4104	
Lime & shale streaks	4104	4171	
Lime & shale	4171	4270	
Lime	4270	4423	
Lime & shale	4423	4465	
Lime	4465	4501	
Lime & shale	4501	4546	
Lime	4546	4602	
Cherty lime	4602	4649	
Lime & shale	4649	4680	
Sand & shale	4680	4722	
Lime	4722	4745 T.D.	D. & A.

TOPS:

Heebner	3612 (-2009)
Toronto	3624 (-2021)
Base Oread	3648 (-2045)
Sand	3739 (-2136)
Lansing	3783 (-2180)
Base Kansas City	4198 (-2593)
Des Moines	4211 (-2608)
Mississippi	4314 (-2710)
Kinderhook	4412 (-2809)
Chattanooga	4503 (-2900)
Viola	4521 (-2918)
Simpson	4633 (-3030)
Arbuckle	4722 (-3119)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

*Paul W. Hesse*  
 Paul W. Hesse

Subscribed and sworn to before me this 16th day of December 1955.

*Duane Jessup*  
 Duane Jessup - Notary Public

My commission expires December 11, 1957.

**PLUGGING**  
 SEC 31 T 31 R 13W  
 BOOK PAGE 24 LINE 11

GENERAL LAND OFFICE  
 WICHITA, KANSAS