

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-007-20851-00.00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County, Sec. 24 Twp. 31S Rge. 12 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C S/2

Lease Owner Raymond Oil Co., Inc.
Lease Name Mott Well No. 1

Office Address One Main Place, Suite 900, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____


Dry Hole

Date Well completed December 31, 19 79
Application for plugging filed December 31, 19 79
Application for plugging approved December 31, 19 79
Plugging commenced December 31, 19 79
Plugging completed December 31, 19 79
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production
19 _____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4329'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	218'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped 40 sacks cement through drill pipe to 300'. Pumped 40 sacks cement through drill pipe to 210'. Made bridge at 40' with 1 sack hulls, plug and 10 sacks cement. Plugged rat hole with 5 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Betty Brandt (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Betty Brandt
910 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of January, 19 80

Rebecca L. Matthews
Rebecca L. Matthews, Notary Public.

My commission expires May 17, 1983

JAN 16 1980

CONSERVATION DIVISION
Wichita, Kansas

ROTARY DRILLERS' LOG

OPERATOR: Raymond Oil Co., Inc. DRILLING COMMENCED: December 18, 1979
One Main Place, Suite 900
Wichita, Kansas 67202

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: December 31, 1979
910 Union Center
Wichita, Kansas 67202

CASING RECORD: 7 Jts. 218' of new 8-5/8" LOCATION: Mott No. 1
cemented with 200 sacks. C S/2.
Section 24-31S-12W
Barber County, Kansas

0 - 218	Red bed
218 - 510	Red bed & shale
510 - 1380	Red bed
1380 - 1758	Red bed, shale & lime
1758 - 1947	Red bed & shale
1947 - 2135	Shale & lime
2135 - 2299	Lime & shale
2299 - 4311	Shale & lime
4311 - 4329	Shale & chert
4329	Rotary Total Depth

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By *John Graves* President

STATE OF KANSAS)
) ss.
SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 15th day of January, 1980.

Betty Brandt
Betty Brandt Notary Public

My commission expires: May 17, 1983

RECEIVED
STATE CORPORATION COMMISSION

JAN 16 1980

CONSERVATION DIVISION
Wichita, Kansas