


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barber County. Sec. 28 Twp. 32S Rge. 12 (E) 12 (W)

Location as "NE/CNW/SW" or footage from lines C-SW SW  
Lease Owner Pickrell Drilling Company  
Lease Name Tedrow Well No. 1  
Office Address 705 Fourth Nat'l. Bank Bldg, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 11-15 19 58  
Application for plugging filed 11-15 19 58  
Application for plugging approved 11-15 19 58  
Plugging commenced 11-15 19 58  
Plugging completed 11-15 19 58  
Reason for abandonment of well or producing formation Dry & Abandoned



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4575 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	200'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with heavy mud to 190', bridge hole and cement with 20 sacks cement. Then heavy mud to 40' below ground level, bridge hole and cement with 10 sacks cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company  
Address 705 Fourth Nat'l. Bank Bldg., Wichita 2, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
C. W. SEBITS (~~employee or contractor~~) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
705 Fourth Nat'l. Bank Bldg, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of November, 1958

My commission expires Dec. 6, 1958  
Martha Scott  
(Martha Scott) Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION

PLUGGING  
FILE SEC 28 T. 32 R. 12  
BOOK PAGE LINE 15

NOV 26 1958  
11:26 58  
CONSERVATION DIVISION  
Wichita, Kansas

**ROTARY DRILLING LOG**

COMPANY: Pickrell Drilling Company

Rotary Drilling Commenced 11-2-58

LOCATION: C-SW SW Sec. 28-32S-12W  
Barber County, Kansas  
Tedrow #1

Rotary Drilling Completed 11-15-58

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: Set 200' (5 jts.) of 8-5/8"OD 22.7# Armco Spiralweld surface casing at 200' with 125 sacks cement. Cement Circulated.

**LOG**

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

Red Rock	200'	Circ. for samples at 4485'
Red Rock & Shale	790'	4495'
Red Bed & Shale	860'	4513'
Shale & Shells	1285'	4515'
Shale	1690'	4525'
Lime	2635'	4575'
Lime & Shale	2955'	
Shale	3110'	
Lime & Shale	3240'	
Lime	3335'	
Shale	3444'	
Shale & Lime	3535'	
Shale	3685'	
Sand & Shale	3830'	
Lime & Shale	3943'	
Lime	4513'	
Mississippi	4525'	
Lime	4575' T.D.	

S.L.M. at 2000 - O.K.  
3000 - O.K.  
4000 - O.K.

Slope Test at 1000' 0° off  
1500' 0° off  
2000' 0° off  
2500' 0° off  
3000' 0° off  
4000' 0° off

**PLUGGING**  
FILE SEC. 28 T. 32 R. 12W  
BOOK PAGE 146 LINE 15

**RECEIVED**  
STATE CORPORATION COMMISSION  
NOV 26 1958  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

**PICKRELL DRILLING COMPANY**  
By C. W. Sebitts  
Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 25th day of November, 19 58, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: Dec. 6, 1958

Martha Scott  
Notary Public  
(Martha Scott)