


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Barber County. Sec. 11 Twp. 32 Rge.      (E) 12 (W)  
Location as "NE/CNW/SW" or footage from lines E/2 E/2 SE/4  
Lease Owner Aylward Drilling Company  
Lease Name Smith "B" Well No. 3  
Office Address 813 1st National Bank Bldg. - Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 25 19 62  
Application for plugging filed July 25 19 62  
Application for plugging approved July 25 19 62  
Plugging commenced July 25 19 62  
Plugging completed July 25 19 62  
Reason for abandonment of well or producing formation     

If a producing well is abandoned, date of last production      19       
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well       
Producing formation      Depth to top      Bottom      Total Depth of Well 4314 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	253'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from      feet to      feet for each plug set.

Heavy mud to 240 feet, set plug and 1/4 sack hulls, then 20 sacks mixed cement through drill pipe - Mud to 40 feet, set plug and 1/4 sack hulls, 10 sacks cement dry, bridged rathole and capped sand with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 5 1962 9.5.62

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Aylward Drilling Company  
Address 813 1st National Bank Bldg. - Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Charles D. Williams (employee of owner) ~~and owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles D. Williams  
813 1st Nat'l Bank Bldg. - Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of September, 1962

My commission expires December 11, 1965  
Duane Jessup Notary Public.

SMITH "B" NO. 3

Casing Record:      Company: Aylward Drilling Company      Location: C E $\frac{1}{2}$  E $\frac{1}{2}$  SE 11-32-12W  
 8 5/8" - 253'      Contractor: Aylward Drilling Company      Barber County, Kansas  
    Commenced: July 13, 1962      Elevation: 1455 DF - 1458 KB  
    Completed: July 25, 1962

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Clay	0	10	Set 8 5/8" surface pipe @ 253' w/290 sacks cement
River Sand	10	30	
Red Rock, hard	30	189	Geological Tops:  Elgin                                3308 Heebner                            3476 Douglas                           3486 Lansing                            3656 Mississippi                       4230  DST 4231-60 Open 70" Rec. 3780' gas in pipe, 240' GCM IBHP 529#/30" - FBHP 481#/30" FP 65#-108#  DST 4260-4314 Open 70" Rec. 120' mud w/trace oil IBHP 200#/30" - FBHP 130#/30" FP 56#-73#
Red Rock	189	253	
Red Rock & Shale	253	755	
Shale & Shells	755	1450	
Lime & Shale	1450	1625	
Lime w/Shale	1625	1765	
Shale & Lime	1765	1960	
Lime & Shale	1960	2075	
Lime mostly w/some Shale	2075	2227	
Lime & Shale	2227	2605	
Shale & Lime streaks	2605	2725	
Shale & Lime	2725	2815	
Lime & Shale	2815	3063	
Shale & Lime	3063	3160	
Lime & Shale	3160	3432	
Lime	3432	3540	
Shale	3540	3550	
Lime & Shale	3550	3763	
Lime	3763	4260	
Chert & Lime	4260	4310	
Lime	4310	4314 T.D.	D & A

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 SEP 5 1962  
 CONSERVATION DIVISION  
 Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

*Charles Williams*

Subscribed and sworn to before me this 8th day of August, 1962

*Paul W. Hesse*  
 Notary Public

My commission expires December 11, 1965