

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007=22,181-00-00

LEASE NAME Mabel Thomas

WELL NUMBER 1-24

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2310 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 24 TWP. 32 RGE. 12 ~~XR~~ (W)

COUNTY Barber

LEASE OPERATOR Rine Exploration Company

ADDRESS Suite #645, 300 W. Douglas, Wichita, KS 67202-2904

PHONE# (316) 262-5418 OPERATORS LICENSE NO. 5020

Date Well Completed 3-31-88

Character of Well _____

Plugging Commenced 3-30-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3-31-88

The plugging proposal was approved on 3-29-88 (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? will be by operator If not, Is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4772

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
Plug #1 set @ 600' with 50 sacks cement through drill pipe
Plug #2 set @ 360' with 40 sacks cement through drill pipe
Plug #3 set @ 40' with 10 sacks cement; 15 sacks in rat hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address PO Box 823, Great Bend, KS 67530

STATE OF KANSAS COUNTY OF BARTON, ss.

JOHN ARMBRUSTER

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) John Armbuster

(Address) Box 823, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 4th day of April, 19 88

Dorothy M Hague
Notary Public

My Commission Expires: 5-5-90



APR - 6 1988

CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S WELL LOG

DATE COMMENCED: March 21, 1988
DATE COMPLETED: March 31, 1988

Rine Exploration Company
Mabel Thomas #1-24
NW¼ NE¼ SW¼
Sec. 24-31-12W
Barber County, KS

ELEVATION: 1490'G.L.

0 - 256' Post Rock, Clay, Shale
256 - 1325' Redbed, Redrock, Shale, Lime Streaks
1325 - 1669' Lime & Shale Streaks
1669 - 2526' Lime & Shale Streaks
2526 - 2777' Lime & Shale Streaks
2777 - 3250' Lime & Shale
3250 - 3457' Shale & Lime
3457 - 3600' Shale, Lime, Sand
3600 - 3717' Lime & Shale
3717 - 4306' Lime
4306 - 4399' Chert & Lime
4399 - 4671' Shale
4671 - 4705' Sand
4705 - 4772' Sand & Shale
4772' RTD

Surface Pipe: Set new
8-5/8", 23# @ 356' with
200 sacks 60/40 pozmix,
2% gel, 3% c.c.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss:

JOHN ARMBRUSTER of lawful age, does swear and state that the facts
and statements herein are true and correct to the best of his knowledge.


John Armbruster
John Armbruster

SUBSCRIBED AND SWORN to before me this 4th day of April, 1988.

RECEIVED
STATE CORPORATION COMMISSION

Dorothy M. Hague
Notary Public

APR - 6 1988



CONSERVATION DIVISION
Wichita, Kansas