

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Barber SEC. 24 TWP. 32 RGE. 12 E/W
 Location as in quarters or footage from lines:
C/NE/SE

Locate Well
 correctly on above
 Section Platt.

Lease Owner CK Oil Co.
 Lease Name Trice Well No. #1
 Office Address 512 Washington - Great Bend, Ks. 67530
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced July 18, 1983
 Plugging completed July 25, 1983
 Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bob Tarbutton
 Producing formation _____ Depth to top _____ bottom T.D. 3730'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	252'	NONE
				5 1/2"	3729'	2788.02'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Dumped sand to 3500' and five (5) sacks cement.
 Shot casing at 2900', and 2770'.
 Pulled eighty-eight (88) joints 5 1/2" casing.
 Squeezed well with four (4) sacks hulls, fifteen (15) sacks gel, fifty (50)
 sacks cement, ten (10) sacks gel, released plug and pumped one hundred
 (100) sacks 60/40 pozmix cement with 2% added gel and 3% calcium chloride.
 Maximum pressure was 750 psi and shutin at 600 psi.


RECEIVED
 STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Rockhold Engineering, Inc. 8-2-83 AUG 02 1983

STATE OF KANSAS COUNTY OF BARTON, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
 JAMES W. ROCKHOLD - Box 698 - Great Bend, Ks.
 (Address) 67530


SUBSCRIBED AND SWORN TO before me this 15 day of August, 1983



Margaret Prosser
 Notary Public.

My Commission expires: _____

AUG 14 1971



24-32-12W
C NE SE

DRILLERS LOG

TRICE NO. 1

GA 1,000,000CFGPD/Coug

CASING RECORD:	OPERATOR:	Beacon Resources Corp.	DESCRIPTION:
8-5/8" @ 252'	CONTRACTOR:	Sage Drilling Co., Inc.	C NE SE
w/250 sax cement	COMMENCED:	October 4, 1970	Sec. 24-32S-12W
TOTAL DEPTH:	COMPLETED:	October 10, 1970	Barber Co., Kansas
3730'			ELEVATION: 1438KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	30	LOG TOPS:
Rock, Shale & Red Bed	30	254	
Red Bed, Shale & Shells	254	784	Elgin Sd 3414
Shale, Red Bed & Shells	784	1485	Heebner 3492
Shale & Lime	1485	1980	Snyderville Sd 3510
Lime & Shale	1980	2745	Douglas Sd 3548
Shale & Lime	2745	3310	LKC 3695
Lime & Shale	3310	3540	
Sand & Shale	3540	3590	
Sand, Shale & Lime	3590	3700	
Shale & Lime	3700	3730	5 1/2" @ 3729' w/150 sax

I certify that this is a true and correct copy of the above log to the best of my knowledge.

- DST (1) 3492-3540
- DST (2) 3537-75
- DST (3) 3575-90

SAGE DRILLING CO., INC.

T. M. McCaul, Jr.
 By _____
 T. M. McCaul, Jr.



Subscribed and sworn to before me this 13th day of October, 1970.

Louise K. Whitted
 Louise K. Whitted, Notary Public

My commission expires:
November 26, 1970.

RECEIVED
STATE CORPORATION COMMISSION

MAR 16 1972

CONSERVATION DIVISION
Wichita, Kansas