

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Barber County, Sec. 22 Twp. 32S Rge. 12W (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW, SW, NW

Lease Owner Aurora Gasoline et al

Lease Name Gillespie Well No. 1

Office Address 308 Wright Bldg., Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 2/8/ 19 51

Application for plugging filed February 8, 19 51

Application for plugging approved February 8, 19 51


Plugging commenced February 8, 19 51

Plugging completed February 8, 19 51

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well 4865 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	164'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from top feet to bottom feet for each plug set.

Mud to 160', set plug and dumped 15 sacks of cement; mud to 30' set plug and ~~dumped 10 sacks of cement~~ dumped 10 sacks of cement to complete

RECEIVED
STATE CORPORATION COMMISSION
2.21.51
FEB 21 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Beardmore Drilling Company, Inc.
Address 603 Petroleum Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Heber Beardmore (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Heber Beardmore

603 Petroleum Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 19th day of February, 19 51

Annette A. Kernally Notary Public

My commission expires 1-19-55

PLUGGING
FILE SEC 28T32R12W
BOOK PAGE 61 LINE 2

Gilaspie No. 1 Well

SW, SW, NW,
Section 22-32S-12W,
Barber County, Kansas

Drilled for: Aurora Gasoline et al
Drilled by: Beardmore Drilling Co., Inc.

Casing Record:

8-5/8" 16 1/2' w/ 100 sacks

Drilling Commenced: January 15, 1951
Drilling Completed: February 8, 1951

Elevation: 1535 D.F.

<u>FORMATION</u>	<u>DEPTH</u>
Cellar	5
/Red rock - Shale	95
Red rock - shells	163
Shale - shells	1415
Shale - lime	1600
Lime	2045
Lime - shale	2160
Lime broken	2270
Lime - shale	2725
Shale - shells-	2840
Lime - shale	3080
Lime	3280
Lime - shale	3723
Sand	3790
Lime - Lansing	4315
Lime - shale	4355
Lime - chert	4385
Lime	4525
Shale & lime	4625
Lime	4710
Shale	4815
Lime	4865 T.D.

D & A

<u>Tops:</u>		
Douglas	3723	
Lansing	3790	
Mississippi	4319	
Viola	4616	
Simpson	4710	
Arbuckle	4810	

DST 3726-38
Open 1 hr
BHP 1100
Recov. 640' Salt Water

DST 4617-36
Open 30 Min
Recov. 30' Sl oil cut mud
No. BHP

DST 4395-4425
Open 30 min
Rec. 30' Sl oil cut mud
NO BHP

DST 4736-53
Open 1 hr
Recov. 10' bil cut mud
No BHP

RECEIVED
STATE CORPORATION COMMISSION
FEB 21 1951
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS
COUNTY OF SEDGWICK

I, the undersigned, being duly sworn on oath state that the above and within statement is a true and correct log and record of the well drilled on the location above-described, to the best of my knowledge and belief.

Alfred Beardmore

Subscribed and sworn to before me this 19th day of February, 1951.

PLUGGING
FILE SEC 22-32R-12W
BOOK PAGE 61 LINE 8

Arnette C. Kennalley
Notary Public

My Commission Expires;
January 19, 1951.