

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15,007-01025-00-01

LEASE NAME Kirkbride OWWO

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2,310 Ft. from S Section Line

4,950 Ft. from E Section Line

SEC. 21 TWP. 32 SRGE. 12 (E or (W))

LEASE OPERATOR EXOK, Inc.

ADDRESS 6410 B. North Santa Fe, Okla. City, OK 73116 COUNTY Barber

PHONE# (405) 840-9196 OPERATORS LICENSE NO. 4581 STATE CORPORATION COMMISSION Completed n/a

Character of Well D&A Plugging Commenced 5/23/89

(Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging Completed 5/23/89

The plugging proposal was approved on 5/17/89 (date)

by Steve Durrant (district #1) (KCC District Agent's Name).

Is ACO-1 filed? no If not, Is well log attached? no

Producing Formation Mississippi Depth to Top 4,373 Bottom 4475 T.D. 4,478

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Mississippi	slight amount of	surface	286	8 5/8"	286'	-0-
	oil & water	surface	4472	5 1/2"	4472	3,800'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged back w/ sand from 4,478' to 4,300' 5 sx cement from 4,300' to 4,260'. Heavy mud to 620'. 400# cottonseed hulls from 620' to 600'. 10 gel from 600' to 565'. 50 sax 60/40 poz + 6% gel from 565' to 390'. 10 gel from 390' to 355'. 100# cotton seed hulls from 355' to 350' 8 5/8" wood plug @ 350'. 100 sax 60/40 poz mix + 6% gel from 350' to surface
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hays Well Service License No. 5429

Address Attica, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: EXOK, Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

James W. Wallis (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Wallis

(Address) 6410 B. North Santa Fe, Okla. City, OK

SUBSCRIBED AND SWORN TO before me this 7th day of June, 19 89

Cynthia K. Rogers
Notary Public

My Commission Expires: 6/9/89