

STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

NOTICE: Fill out completely and return to Cons. Div. office within 30 days.

API NUMBER 15-007-21-518

LEASE NAME Snyder

WELL NUMBER 2

4950 Ft. from S Section

890 Ft. from E Section Line

SEC. 21 TWP. 32S RGE. 12W (E) or (W)

COUNTY Barber

Date Well Completed 11-18-82

Plugging Commenced 4-15-94

Plugging Completed 4-21-94

LEASE OPERATOR American Energies Corp.

ADDRESS 155 N. Market #710

PHONE# (316) 263-5785 OPERATORS LICENSE NO. 5399

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-13-94 (date)

by District #1- Lacy (KCC District Agent's Name)

Is ACC-1 filed? yes If not, Is well log attached? yes

Producing Formation simpson Depth to Top 4796 Bottom 4871 T.O. 4900

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	water	0	401	8 5/8	401	none
	water	0	4900	4 1/2	4887	3520

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from feet to feet each section.

Sand back 50 ft over perforations to 4740 ft, spot 4 sx plug, pull pipe at 3520 and pull to surface, pump 300 lbs hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs hulls, 8 5/8 wiper plug, 100 sx cement Allied #6338 60/40-6% Gel.

Name of Plugging Contractor VAL Energy, Inc. License No. 5822

Address Box 322 Hasyville, Ks. 67060

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Energies Corp.

STATE OF Kansas COUNTY OF Sedgwick, ss.


Todd Allam (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well, and the same are true and correct, so help me God.

(Signature) Todd Allam

(Address) Wichita, MAY 02 1994

SUBSCRIBED AND SWORN TO before me this 25th day of April 1994

Gary D. Stearns
Notary Public



USE ONLY ONE SIDE OF EACH FORM