

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-21383-06-00

LEASE NAME EBY

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

2970 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 16 TWP 32 RGE. 12W (E) or (W)

COUNTY Barber

Date Well Completed 2-15-82

Plugging Commenced 4-18-95

Plugging Completed 4-27-95

LEASE OPERATOR Farrar Pump & Supply

ADDRESS Box 209 Medicine Lodge, Ks. 67104

PHONE (316) 886-3763 OPERATORS LICENSE NO. 003399

Character of Well gas

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-14-95 (date)

by Dodge City, Office (XCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? N/A

Producing Formation Miss. Depth to Top 4428 Bottom 4684 T.O. 4500

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	water	0	401	8 5/8	401	None
	water	0	4930	4 1/2	4930	2535

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Sand back with rock to 4313', spot 4 sx plug of cement, pull pipe at 2535 ft. Pumped 300 lbs hulls 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs hulls, 100 sx cement. Allied #1325

Name of Plugging Contractor VAL Energy, Inc. License No. 5822

Address Box 322 Haysville, Ks. 67060

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Farrar Pump & Supply

STATE OF Kansas COUNTY OF Sedgwick

K Todd Allam


(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) K Todd Allam

(Address) Wichita, Ks.

SUBSCRIBED AND SWORN TO before me this 1st day of May, 19 95



RECEIVED
STATE CORPORATION COMMISSION
MAY 02 1995 5:29

My Commission Expires:
USE ONLY ONE SIDE OF EACH FORM