

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Barber

County. Sec. 14 Twp. 32 Rge. (E) 12 (W)

Location as "NE/CNWxSWx" or footage from lines SW NE NE  
Lease Owner Aylward Drilling Company  
Lease Name Smith Well No. 2  
Office Address 813 1st National Bank Bldg. - Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 29 1960  
Application for plugging filed August 29 1960  
Application for plugging approved August 29 1960  
Plugging commenced August 29 1960  
Plugging completed August 29 1960  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hample  
Producing formation None Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	255'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with mud to 200 feet  
Set plug at 200 feet with 20 sacks cement  
and 1/4 sack hulls  
Filled with mud to 35 feet  
Set plug at 35 feet with 10 sacks cement  
and 1/4 sack hulls  
Bridged rat hole and plugged with 5 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 21 1960  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Aylward Drilling Company  
Address 813 1st National Bank Bldg. - Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Charles D. Williams (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles D. Williams  
813 1st Nat'l Bank Bldg. - Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of September, 1960

Duane Jessup  
DUANE JESSUP Notary Public.

My commission expires December 11, 1961

SMITH NO. 2

Casing Record:	Company: Aylward Drilling Company	Location: SW NE NE 14-32-12W
8 5/8" - 250'	Contractor: Aylward Drilling Company	Barber County Kansas
	Commenced: August 18, 1960	
	Completed: August 28, 1960	Elevation: 1453 R.B.

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Sand	0	45	Set 8 5/8" surface pipe @ 250'
Red Bed & Red Rock	45	200	w/275 sacks cement.
Red Rock	200	255	
Red Bed	280	800	Geological Tops:
Red Bed & Shale	800	1050	
Shale	1050	1430	Elgin 3316
Shale & Shells	1430	1480	Heebner 3494
Shale & Lime	1480	1600	Lansing 3674
Lime	1600	1725	Miss. 4242
Shale & Lime	1725	1850	
Lime & Shale	1850	2147	
Shale & Lime	2147	2270	DST 4243-64 Open 1 hr.
Shale & Shells	2270	2490	Rec. 180' OCM, Gas/46" TSTM
Shale & Lime	2490	2980	IBHP 1270# - FBHP 1120#
Lime & Shale	2980	3086	FP. 0#-0#
Shale w/some Lime	3086	3175	
Shale & Lime	3175	3300	DST 4255-4325 Open 1 hr.
Sand & Shale	3300	3455	Rec. 190' OCM
Shale & Sand	3455	4575	IBHP 1480# - FBHP 1020#
Shale & Lime	3575	3700	
Lime & Shale	3700	3770	
Lime	3770	3981	
Lime w/Shale Breaks	3981	4040	
Lime	4040	4110	
Lime & Shale	4110	4264	
Chert	4264	4325 T.D.	D & A

**RECEIVED**  
STATE CORPORATION COMMISSION  
OCT 21 1960  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

*Charles D. Williams*  
\_\_\_\_\_

Subscribed and sworn to before me this 31st day of August, 1960

*Duane Jessup*  
\_\_\_\_\_ DUANE JESSUP Notary Public

My commission expires December 11, 1961