


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

BARBER County. Sec. 14 Twp. 32S Rge. (E) 12 (W)
Location as "NE/CNW/SW" or footage from lines. SW SW SE
Lease Owner E. H. Adair, et al,
Lease Name Cottrell-Smith Well No. 1.
Office Address 1019 East Second Street, Wichita 7, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Dry-hole.
Date well completed 11-24-1956 19__
Application for plugging filed 11-24 19 56
Application for plugging approved 11-24 19 56
Plugging commenced 11-24 19 56
Plugging completed 11-24 19 56
Reason for abandonment of well or producing formation dry.

If a producing well is abandoned, date of last production -- 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 8, Pratt, Kansas.
Producing formation -- Depth to top --- Bottom --- Total Depth of Well 4682 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
(Copy of driller's log attached hereto)						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from --- feet to --- feet for each plug set.

Placed bottom-plug at 200 feet with 20 sacks of victory cement, and top plug at 35 feet with 10 sacks of cement. Filled to surface with dirt.

RECEIVED
STATE CORPORATION COMMISSION
NOV 7 - 1956 12-7-56
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor E. H. Adair Oil Company
Address 1019 E. Second Street, Wichita 7, Kansas.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
K. W. Johnson (employee of owner) ~~or (owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K. W. Johnson
1019 E. Second Street, Wichita 7, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of December, 19 56.

L. Hill
Notary Public.

My commission expires September 15, 1957.

PLUGGING
FILE SEC. 14 T. 32 R. 12W
BOOK PAGE 119 LINE 23

E. H. Adair Oil Company
 1019 E. Second Street
 Wichita 7, Kansas.

E. H. Adair Oil Company, et al,
 Cottrell-Smith No. 1
 SW SW SE of
 Sec. 14-Twp. 32S.-R. 12 West
 Elevation: 1512 K.B.

Comm.: 11-4-56
 Comp.: 11-24-56
 Contractor:
 E. H. Adair -Rig No. 1
 8-5/8 @ 200 ft. w/175 sx.
 D. & A.

All figures indicate bottoms of Formations

Shale	to 100	Sand	to 3724
Shale & shells	1503	Shale & sand	3740
Lime	2090	Lime	3743
Lime & shale	3033	Shale	3747
Lime	3220	Lime, K.C.	4126
Shaley lime	3275	Shale, black	4130
Shale	3340	Lime	4162
Lime & shaley lime	3372	Shale, black	4166
Shale	3502	Lime, with some	
Lime & little shale	3529	shale streaks	4310
Shale, dark	3536	Chert	4452
Lime	3545	Lime	4487
Shale, black	3547	Shale	4567
Lime	3552	Dark shale	4602
Shale	3651	Dolomitic Cherty	
Sand	3662	lime	4676
Sandy shale	3707	Sand	4682
		T.D.	4682

Electric Log Tops

Elgin Zone	3370
Heebner	3535
Douglas Sand	3564
Brown Lime	3737
Lansing, K.C.	3744
Mississippi	4307
Kinderhook	4486
Chattanooga	4566
Viola	4602
Simpson Sand	4676

AFFIDAVIT

State of Kansas)
 County of Sedgwick) ss:


K. W. Johnson, of lawful age, being first duly sworn on oath
 deposes and says:
 That he is the geologist for the E. H. Adair Oil Company,
 Wichita, Kansas, and that he has read the above and foregoing drilling-log
 covering the Cottrell-Smith No. 1 test-well, located in Section 14-32-12 W.
 Barber County, Kansas, and that the same is true and correct.

K. W. Johnson
 K. W. Johnson.

Subscribed and sworn to before me, this 30th day of November,,
 1956.

L. Hill
 L. Hill - Notary Public.

My Commission Expires:
 September 15, 1957.



RECEIVED
 STATE CORPORATION COMMISSION

DEC 7 - 1956

CONSERVATION DIVISION
 WICHITA, KANSAS