


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Barber County. Sec. 9 Twp. 31 Rge. 13 NE (W)

Location as "NE/CNW&SWK" or footage from lines C-NE-NE
Lease Owner National Petroleum Company
Lease Name Maddix Well No. 1
Office Address 501 1st Nat'l Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed 8/10 19 61
Application for plugging filed 8/10 19 61
Application for plugging approved 8/10 19 61
Plugging commenced 8/10 19 61
Plugging completed 8/10 19 61
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4505 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>None</u>				<u>8-5/8"</u>	<u>309'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud from TD to 300'. Plug at 300'. 15 sacks of cement and 1/4 sack of hulls on bottom plug. Mud to 35'. Plug at 35'. 10 sacks of cement and 1/4 sack of hulls on top plug. Mud to surface. 2 sacks of cement in cellar.

RECEIVED
STATE CORPORATION COMMISSION

AUG 15 1961

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Fortune Oil and Gas, Inc.
Address 918 Central Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Robert L. Jones (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
918 Central Building - Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of August, 19 61

My commission expires July 25, 1964 [Signature] Notary Public.

DRILLERS LOG

OPERATOR: NATIONAL PETROLEUM COMPANY
CONTRACTOR: FORTUNE OIL & GAS, INC.
WELL: MADDIX #1
LOCATION: C-NE-NE Sec. 9-318-13W
BARBER COUNTY, KANSAS
COMMENCED: 7/25/61
COMPLETED: 8/10/61

0	3450	Shale and lime
3450	3532	Lime
3532	3774	Lime and shale
3774	3816	Shale and sand
3816	4399	Lime
4399	4498	Lime and shale
4498	4505	Lime
	4505	Total Depth - D and A

RECEIVED
STATE CORPORATION COMMISSION

AUG 15 1961

CONSERVATION DIVISION
Wichita, Kansas

Set 8 5/8" surface casing @ 309' with 225 sacks of cement.

I, Robert L. Jones, do hereby certify that the above and foregoing is a true and correct copy of the log of the Maddix #1, located in the C-NE-NE of Sec. 9, 318-13W, Barber County, Kansas, as reflected by the files of Fortune Oil & Gas, Inc.


Robert L. Jones

State of Kansas)
Sedgwick County) ss:

Subscribed and sworn to before me, a Notary Public, in and for the County of Sedgwick, State of Kansas this 14th day August, 1961.

My commission expires:

July 25, 1964


Notary Public