


15.007-20787.00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Barber County, Sec. 28 Twp. 31S Rge. 12 E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
175' N C NE NE  
Lease Owner Graves Drilling Co., Inc.  
Lease Name Wheelock Well No. 1  
Office Address 910 Union Center, Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above  
Section Plat

Date Well completed September 18, 1979  
Application for plugging filed September 18, 1979  
Application for plugging approved September 18, 1979  
Plugging commenced September 18, 1979  
Plugging completed September 18, 1979  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen, Pratt, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4330'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	204'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pumped 40 sacks cement through drill pipe to 210'. Pushed plug and 1/2 sack hulls to 40' with 12 sacks cement. Plugged rat hole with 3 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
John C. Graves (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

910 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of September, 19 79

Betty Brandt  
Betty Brandt Notary Public.

My commission expires May 9, 1983

ROTARY DRILLERS' LOG

OPERATOR: Graves Drilling Co., Inc. COMMENCED: September 10, 1979  
910 Union Center  
Wichita, Kansas 67202

CONTRACTOR: Graves Drilling Co., Inc. COMPLETED: September 18, 1979  
910 Union Center  
Wichita, Kansas 67202

CASING RECORD: 5 Jts. 204' of used 8-5/8" LOCATION: Wheelock No. 1  
cemented with 185 sacks 175' W C NE NE  
Section 28-31S-12W  
Barber County, Kansas

-----

0 - 1075	Red bed
1075 - 1777	Red bed & shale
1777 - 2178	Shale & lime
2178 - 2524	Lime & shale
2524 - 4162	Shale & lime
4162 - 4257	Lime & shale
4257 - 4295	Shale & lime
4295 - 4330	Chert
4330	Rotary Total Depth

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 26 1979  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John Graves President

STATE OF KANSAS     )  
                          )  
SEDCWICK COUNTY    )     ss.



Subscribed and sworn to before me, a Notary Public, this 25th day of September,

Betty Brandt  
Betty Brandt Notary Public

My commission expires: May 9, 1983