

OF KANSAS
CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-077-20,252

LEASE NAME Long

WELL NUMBER #1

Ft. from S Section Line

Ft. from E Section Line

SEC. 16 TWP. 31S RGE. 8

COUNTY Harper

Date Well Completed 3-17-74

Plugging Commenced 11-14-94

Plugging Completed 11-16-94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 3107 N. Cypress, Wichita, KS 67226-4003

PHONE# (316) 636-2737 OPERATORS LICENSE NO. 5003

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Steve VanGieson (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Mississippian Depth to Top _____ Bottom T.D. 4408'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	208'	8-5/8"	208'	None
		0	4391'	5-1/2"	4391'	2034'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Plugged and abandon using 60/40 Pozmix, 4%gel. Set 1st plug @ 1365' w/30 sx; 2nd plug 875' w/30 sx; 3rd plug set @ 261' w/115 sx and circulate to surface. Top off with 25 sx. Complete 11-16-94.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shawnee Well Service License No. 20346

Address P. O. Box 781624 Wichita, KS 67278-1624

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.


McCoy Petroleum Corporation (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 3107 N. Cypress Wichita, KS 67226-4003

SUBSCRIBED AND SWORN TO before me this 12 day of December



X Deborah Ann Paulus Notary Public

January 8, 1996

RECEIVED
CORPORATION COMMISSION
12-14-94
DEC 14 1994
CORPORATION COMMISSION
WICHITA, KANSAS
REV 1985