

15-077-000260000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Harper County. Sec. 16 Twp. 31S Rge. 8 (E) (W)

Location as "NE/CNW4SW4" or footage from lines SW/SW/NW

Lease Owner Mull Drilling Company, Inc.

Lease Name Critser Well No. #1

Office Address 6405 East Kellogg, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19____

Application for plugging filed Yes 19____

Application for plugging approved Yes 19____

Plugging commenced _____ 10-11 19 57

Plugging completed _____ 10-16 19 57

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Mr. M.A. Rives

Name of Conservation Agent who supervised plugging of this well

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4405' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		3,548'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into T.D. 4405'.

Plugging started 10-11-57. Finished 10-16-57.

Plugged off bottom and dumped 5 sacks cement with bailer. Shot 5 1/2" casing at 3,548'. Mixed and circulated mud. Pulled pipe out of hole and plugged well with mud to 200'. Set permanent rock bridge and dumped 25 sacks cement. Filled hole with mud to 35', set and mixed 10 sacks cement for cap on well. Well completed.

RECEIVED
OCT 22 1957
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221, Great Bend, Kans. (Address)

SUBSCRIBED AND SWORN to before me this 21st day of October, 1957.

My commission expires November 8, 1960.

Betty S. Edmer
Notary Public.

PLUGGING
SEC 16 T 31 R 8W
BOOK PAGE 50 LINE 26

file copy

ROTARY DRILLERS LOG

COMPANY : Purcell-Mull Drilling Co., Inc. ROTARY DRILLING COMMENCED: 11-5-55
 Wichita, Kansas

CONTRACTOR : Purcell-Mull Drilling Co., Inc. ROTARY DRILLING COMPLETED: 11-17-55
 Wichita, Kansas

CASING RECORD : Set B 5/8" @ 160' cemented with LOCATION: CRITZER #1
 125 sacks cement. SW 3/4 NW of Sec. 16-31S-8W,
 Harper County, Kansas

Set C 1/2" @ 1405' cemented with
 150 sacks Pozmix

(Figures indicate bottom of formation - measurements from top of Rotary Bushing)

Sand	40	Lime & Shale	3268
Red Rock	160	Lime	3337
Red Bed & Shells	450	Lime & Shale	3414
Shale & Shells	1280	Lime, Shale & Sand	3548
Shale & Lime	1410	Sandy Lime & Shale	3656
Lime	1515	Lime	3818
Lime & Shale	1978	Lime & Shale	3976
Shale & Lime	2615	Lime	4143
Lime & Shale	2920	Lime & Shale	4272
Lime, Shale & Sand	3051	Lime	4308
Lime	3145	Shale & Lime	4356
		Lime (Mississippi)	4405 R.T.D.

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Purcell-Mull Drilling Co., Inc.

[Signature]
 _____, SECRETARY
 FRANK H. PURCELL

STATE OF KANSAS)
) SS
 COUNTY OF SEDWICK)

Subscribed and sworn to before me this 21st day of November, 1955.

[Signature]

 NOTARY PUBLIC

MY COMMISSION EXPIRES: January 28, 1957.

*11-22-55
 Sent to myra & Herb
 by*

RECEIVED
 STATE CORPORATION COMMISSION

OCT 3 - 1957
 10-3-57
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC. 16 T. 31 R. 8W
 BOOK PAGE 50 LINE 26