

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County, Sec. 15 Twp. 31S Rge. 11W E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
C SE NW NW


Lease Owner Mid-Continent Energy Corporation
Lease Name Brenner Well No. 1
Office Address 120 Bldg.-Suite 712, 120 S. Market,
Character of Well (Completed as Oil, Gas or Dry Hole) Wichita
Dry Hole KS 67202

Date Well completed June 14, 1980
Application for plugging filed Verbal Application 19
Application for plugging approved Verbal Approval 19
Plugging commenced June 14, 1980
Plugging completed June 14, 1980
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William T. Owen
Producing formation Depth to top Bottom Total Depth of Well 13,980'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	288'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud from 3,980 ft. (rotary total depth) to 300 ft. Set plug at 300 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 300 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services
410 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent ~~XXXXXXXXXXXXXXXXXXXXXXXXXXXX~~
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
251 N. Water - Suite 10, Wichita, KS
(Address) 67202

SUBSCRIBED AND SWORN TO before me this 23rd day of June, 1980

Elsie Willison
Elsie Willison - Notary Public.

My commission expires July 25, 1982

STATE CORPORATION COMMISSION

JUN 27 1980

6-27-80

CONSERVATION DIVISION
WICHITA, KANSAS

KANSAS DRILLERS LOG

COMPANY Mid-Continent Energy Corporation
 FARM Brenner NO. 1

SEC. 15 T. 31S. 11W
 LOC. C- SE NW NW

COUNTY Barber

ROTARY TOTAL DEPTH 3,980'
 COMM. June 7, 1980 COMP. June 14, 1980
 CONTRACTOR H-30, Inc. (Rig #11)
 ISSUED June 23, 1980

CASING

10 3/4"
 8 5/8" Set at 288' cemented w/225 sxs cement
 5 1/2"
 4 1/2"

ELEVATION 1,786' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Bed	292'
Shale	1,600'
Shale and Lime	1,895'
Lime and Shale	2,418'
Shale and Lime	2,568'
Lime and Shale	2,825'
Shale and Lime	2,938'
Lime and Shale	3,100'
Lime	3,980'
Rotary Total Depth	3,980'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting
 Dean Britting

State of Kansas)
) SS:
 County of Sedgwick)

Subscribed and Sworn to before me a Notary Public in and for said county and state this 23rd day of June, 1980.

Elsie Willison
 Elsie Willison - Notary Public

My Commission Expires:
 July 25, 1982

JUN 27 1980
 6-27-80
 CONSERVATION DIVISION
 Wichita, Kansas