


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Barber County. Sec. 12 Twp. 31S Rge. 15 (E) 15 (W)  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines C, NE, SE, NE,  
Lease Owner R. C. Patton Co., & Others  
Lease Name Riepe Well No. 1  
Office Address 612 Orpheum Bldg. Wichita 2, Kansas.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed January 23rd, 19 49  
Application for plugging filed January 20th 19 49  
Application for plugging approved January 20th 19 49  
Plugging commenced January 23rd 19 49  
Plugging completed January 23rd 19 49  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough  
Producing formation Depth to top Bottom Total Depth of Well 4723 Feet  
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				15" O.D.	95 Ft	None
				8 5/8 "	754 Ft	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled Hole with Heavy Mud to 200ft. Bridge Plug, 15 Sacks Cement,  
Filled Hole with Heavy Mud to 30ft from base collar Plug with 10  
Sacks, Cemented throug Drill Pipe.



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to R. C. Patton Co.,  
Address 612 Orpheum Bldg. Wichita 2, Kansas.

STATE OF Kansas COUNTY OF Sedgewick, ss.  
R. C. Patton (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. C. Patton  
612 Orpheum Bldg. Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 26th day of January 19 49  
Notary Public.

My commission expires Oct. 4th 1952 22-5133-s 9-48-10M

PLUGGING  
FILE SEC 12 T 31 R 15  
BOOK PAGE 80 LINE 43

R. C. Patton Co., & Others  
Riepe Well #1

Total Depth 4723  
Comm. 12/23/48  
Comp 1/23/49  
Contractor R. C. Patton Co.,

Located Ctr. NE, SE, NE, Sec 12,  
T31S, R15W. Barber Co., Kansas.  
CASING RECORD  
95ft. 13" O. D. Casing At 95ft.  
With 140 Sacks Cement  
8 5/8" O. D. Casing at 754 Ft.  
With 400 Sacks Cement

Celler	10
Water Sand	43
Shale Red	103
Red Shale & Shells	525
Shale & Shells	1075
Salt	1110
Shale & Shells	1305
Shale & Lime	1500
Shale & Salt	1600
Shale & Lime	1935
Lime	2023
Shale & Lime	2215
Lime	2270
Lime Cherty	2385
Lime & Shale	2345
Lime	2475
Lime & Shale	2555
Shale	2565
Shale & Lime	2690
Shale	2905
Shale & Lime	3040
Lime	3585
Lime & Shale	3650
Lime Sandy	3715
Lime & Shale	3835
Lime	3970
Lime Chat	4010
Lime	4132
Shale & Lime	4164
Lime	4325
Shale & Lime	4443
Lime	4453
Lime Cherty	4497
Chert	4532
Lime & Chert	4563
Shale Sandy	4700
Lime	4723
Total Depth	4723

TOPS

Heebner	3610
Douglass	3677 to 3723
Douglass	3774 to 3781
Lansing	3802
Massey Zone	4226 to 4232
Kinderhook	4323
Maq.	4422
Cr. Viola	4471
Cherty "	4491
Sim. Shale	4557
Sim. Sand	4566
Arbuckle	4661

RECEIVED

Conservation Div.

JAN 27 1949

STATE CORPORATION  
COMMISSION  
KANSAS

STATE OF Kansas COUNTY OF Sedgewick, ss

I, the undersigned, being duly sworn, on oath state that the above statement and log is a true and correct record and log of the well drilled at the location above described.

R. C. PATTON CO.,

By R. C. Patton

Subscribed and sworn to before me this 26th day of January, 1949

R. P. Anderson  
Notary Public

My Commission expires Oct 4th 1952

PLUGGING  
FILE SEC 12 T 31 R 15 W  
BOOK PAGE 80 LINE 43