

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 7 Twp. 31S Rge. 15W (E) (W)

Location as "NE/CNWxSWx" or footage from lines C SW/4

Lease Owner The Superior Oil Company

Lease Name Kitner Unit Well No. 1

Office Address Box 690, Chickasha, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 11, 19 59

Application for plugging filed November 10, 19 59

Application for plugging approved November 10, 19 59

Plugging commenced November 10, 19 59

Plugging completed November 11, 19 59

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot

Producing formation None Depth to top _____ Bottom _____ Total Depth of Well 4850 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi Chert	-	4623	(-2704)	8-5/8	929'	None
Viola Lime		4841	(-2922)			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Equalized 50 sack cement plug with pipe at 4765.
Equalized 25 sack cement plug with pipe at 870 ft. Checked top of plug at 875 ft.
Equalized 20 sack plug with pipe at 90 ft. Checked top of plug at 10'.
Filled casing to surface with cement. Welded on 1/2" steel cap.

RECEIVED
STATE CORPORATION COMMISSION

DEC 10 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barbour Drilling Company
Address 1645 East 21 st. St., Tulsa, Oklahoma

STATE OF Oklahoma, COUNTY OF Grady, ss.
O. V. Sivage, Petroleum Engineer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) O. V. Sivage
Box 690, Chickasha, Oklahoma
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of December, 19 59

My commission expires Sept. 15, 1960
M. J. Fiegel Notary Public.



RECEIVED
STATE CORPORATION COMMISSION
NOV 12 1959
CONSERVATION DIVISION
Wichita, Kansas

THE SUPERIOR OIL COMPANY

Drillers Log: Kitner Unit #1
C SW/4 Section 7-31S-15W (Glick Field)
Barber County, Kansas

Figures below indicate bottom of formation:

Red beds	0 - 115'
Shells & red beds	816
Shale & red beds	865
Shale & shells	1,480
Salt, shale & shells	1,600
Shale & shells	1,865
Shale	2,010
Lime & shale	2,160
Lime	2,340
Lime & shale	2,385
Lime	2,570
Lime & shale	2,810
Shale & shells	2,860
Shale & lime	3,220
Lime	3,400
Shale & lime	3,490
Lime	3,890
Shale & lime	4,100
Lime	4,335
Shale & lime	4,623
Chert & shale	4,770
Shale & lime	4,850
T.D.	4,850 (D.&A.)