

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Barber SEC. 31 TWP. 31S RGE. 15 XYW  
Location as in quarters or footage from lines:  
2340 FNL 455 FWL

|  |  |  |  |
|--|--|--|--|
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |

Locate Well  
correctly on above  
Section Platt.

Lease Owner Texas Oil and Gas Corporation  
Lease Name Rusk Well No. G-1  
Office Address Suite 300 - 200 W. Douglas - Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry  
Date Well Completed 9-20-82  
Application for plugging filed 11-12-82  
Plugging commenced 12-20-82  
Plugging completed 12-30-82  
Reason for abandonment of well or producing formation Dry

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Lutini  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 5,020  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

| Formation | Content | From | To | Size  | Put in | Pulled Out |
|-----------|---------|------|----|-------|--------|------------|
|           |         |      |    | 8 5/8 | 379    | None       |
|           |         |      |    | 4 1/2 | 4924   | 2996       |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set. Plugged back at 4,992.  
Sand from 4,992 to 4,880  
4 sacks cement from 4,880 to 4,850  
Pumped in 3 sacks hulls - 20 sacks jell - 100 sacks cement - 20 sacks jell  
1 sack hulls - Dropped plug - 125 sacks 50-50- POZ 4% jell - 3% C. C.  
Started pumping 9:30 - MAX pressure 350 - Shut in 350 - 10:30

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation

STATE OF Kansas COUNTY OF Barber, ss.  
Clino B. Morgenstern (employee of ~~owner~~) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Clino B. Morgenstern  
Medco Petroleum, Inc.  
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of January 19 83

Jessie Hamilton  
Notary Public.

My Commission expires: April 4, 1986

JAN 10 1983

Conservation Division  
Wichita Kansas