

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
500 Bittling Building
Wichita, Kansas

Barber County, Sec. 9 Twp. 30 Rge. (E) 15 (W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines SW NW
Lease Owner Tenneco Oil Company
Lease Name L. M. Lee "A" Well No. 2
Office Address 2000 Classen Building, Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-25 19 66
Application for plugging filed 1-25 19 66
Application for plugging approved 1-26 19 66
Plugging commenced 1-25 19 66
Plugging completed 1-25 19 66
Reason for abandonment of well or producing formation Dry Hole

NORTH

X			

Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Elving
Producing formation Depth to top Bottom Total Depth of Well 4700 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded to 290', set bridge plug w/2 sx of cement and 3/4 hulls, set 23 sx of cement on top of plug, mudded to 40', set 10 sx of cement to top. Put 2 sx of cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

FEB 24 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Tenneco Oil Company
Address 2000 Classen Building, Oklahoma City, Oklahoma 73106

STATE OF OKLAHOMA, COUNTY OF OKLAHOMA, ss.
John G. Lemons (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John G. Lemons
John G. Lemons, District Office Supv.
2000 Classen Building, Oklahoma City, Oklahoma
(Address)

SUBSCRIBED AND SWORN TO before me this 18 day of February, 19 66

Allen D. Ashley
Notary Public.

My commission expires 5-24-68

CONTRACTOR'S
WELL LOG

Tenneco Oil Company &
Burch Exploration, Inc.
#2 Lee "A"
C SW NW Sec. 9-30S-15W
Barber County, Kansas

Set 8-5/8" @ 304 with 235 sacks Pozmix.
Commenced: 1-10-66
Completed: 1-25-66
Elevation: 1930 KB

D & A

306 Clay
635 Red Clay
1430 Red Bed, Shale & Shells
2245 Shale & Shells
2375 Shale, shells & Lime
2475 Lime & Shale
2715 Lime
4110 Lime & Shale
4495 Lime
4539 Lime & Shale
4570 Lime
4630 Lime-Shale-Chert
4674 Lime
4680 Lime & Chert
4700 Cherty Lime

Tops

Heebner	3848 (-1918)
Toronto	3864 (-1934)
Douglas Shale	3886 (-1956)
Brown Lime	4024 (-2094)
Lansing Kansas City	4042 (-2112)
Massey	4474 (-2544)
Conglomerate	4568 (-2638)
Maquoketa	4600 (-2670)
Viola	4614 (-2684)


4700 Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION


MAR 25 1966

STATE OF KANSAS)
) ss:
COUNTY OF SEDGWICK)

I, Earl M. Burch, President of Burch Exploration, Inc. being duly sworn on oath, state: That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.


Earl M. Burch, President

Subscribed and sworn to before me this 8th day of February, 1966.


Minnie E. Matson, Notary Public

My commission expires: June 18, 1968