

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County, Sec. 11 Twp. 30S Rge. 15 E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines
150' E NE of NE SE

Lease Owner Gear Petroleum Co.
Lease Name Bible Well No. 1
Office Address 1325 Vickers, KSB&T Bldg., Wichita, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole
Date Well completed August 27, 1976
Application for plugging filed August 27, 1976
Application for plugging approved August 27, 1976
Plugging commenced August 27, 1976
Plugging completed August 27, 1976
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plot

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation Depth to top Bottom Total Depth of Well 3406'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Filled hole with heavy mud to 250 feet. Pumped 35 sacks of cement through drill pipe
with pump truck. Pushed plug and $\frac{1}{2}$ sack hulls to 40' and pumped 15 sacks of cement
through drill pipe with pump truck to base of well cellar. Plugged rat hole with
5 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 02 1976

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.
910 Union Center, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK ss.
John C. Graves (employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God

(Signature) John C. Graves
910 Union Center, Wichita, Kansas 67202
(Address)

Subscribed and sworn to before me this 1st day of September, 1976.

My commission expires May 9, 1977

Betty Brandt
Betty Brandt Notary Public

ROTARY DRILLERS' LOG

OPERATOR: Gear Petroleum Co. DRILLING COMMENCED: 22 Aug. 1976
 1325 Vickers-KSBT Bldg.
 Wichita, Kansas 67202

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: 27 Aug. 1976
 910 Union Center
 Wichita, Kansas 67202

CASING RECORD: 6 Jts. 251' of used 8-5/8" LOCATION: Bible No. 1
 cemented with 180 sacks NE SE
 Section 11-30S-15W
 Barber County, Kansas

0 - 350 Red bed
 350 - 1854 Shale
 1854 - 2135 Shale & shells
 2135 - 2340 Lime
 2340 - 2550 Lime & shale
 2550 - 3310 Shale & lime
 3310 - 3406 Lime
 3406 Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 02 1976
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By Court Graves

STATE OF KANSAS)
) SS:
 SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 1st day of September, 1976

My commission expires: June 17, 1977

Ruth N. Benjamin
 Ruth N. Benjamin Notary Public