


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barber County. Sec. 3 Twp. 32S Rge. 12 (E) (W) X

Location as "NE/CNW/SW" or footage from lines C SW NW
Lease Owner Mull Drilling Company, Inc.
Lease Name Wheelock Well No. 1
Office Address 1625 Wichita Plaza Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed 7-27-67 19____
Application for plugging approved 7-28-67 19____
Plugging commenced 7-29-67 19____
Plugging completed 8-10-67 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4297 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	239	None
				4 1/2	None	2178

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in. Killed gas. Sanded to 4200'. Dumped 3 sacks of cement.
Cleaned out cellar. Rigged up. Working pipe.
Working pipe. Shot pipe at 3650'.
Working pipe. Circulating. Globe Cementing spotted 80 bbl of oil.
Working pipe. Shot pipe at 3500' - 3400' - 3200' - 3000' - 2800' - 2600' - 2400' - 2300' and 2220'.
Pulling pipe. Pushed plug to 230' rock bridge. Dumped 6 sacks of cement.
Bailing hole dry. Dumped 19 sacks of cement. Filled hole and rock bridge. Capped well with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. J. O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14 day of August, 19 67

My commission expires May 27, 1969

Notary Public.

ROTARY DRILLER'S LOG

COMPANY: Mull Drilling Company, Inc. ROTARY DRILLING COMMENCED: 3/11/64
 Wichita, Kansas

CONTRACTOR: Mull Drilling Co., Inc. ROTARY DRILLING COMPLETED: 3/25/64
 Wichita, Kansas

CASING RECORD: Set 239' of 8 5/8" Surf. Csg. LOCATION: Wheelock #1
 w/200 sx. C SW NW 3-32S-12W
 Set 4297' 4 1/2" Csg. Barber County, Kansas
 w/125 Sx.

(Figures indicate bottom of formation; measurements from top of Rotary Bushing.)

385' Red Bed
 1167' Red, Bed, Blue Shale Sand
 1351' Shale
 3083' Lime w/Shale
 3195' Sandy Lime & Shale
 3390' Chalky Lime & Shale
 3508' Sandy Lime & Shale
 4250' Lime & Shale
 4275' Mississippi
 4322' Cherty Mississippi w/Lime
 4389' Mississippi Lime
 4549' Lime w/Shale
 4670' Lime
 4605' Lime w/Shale
 4631' Simpson & Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 28 1967
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

MULL DRILLING COMPANY, INC.
Joseph B. Brungardt, Jr.
 Joseph B. Brungardt, Jr.

STATE OF KANSAS
 COUNTY OF SEDGWICK

} Subscribed and sworn before me this 6th day of April, 1964.

Lola L. Foster
 Lola L. Foster, Notary Public



Commission expires April 17, 1966.