

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

BARBER County. Sec. 3 Twp. 32S Rge. 12W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NE SE

Lease Owner Mull Drilling Company

Address: 670 Fourth Nat'l. Bldg., Wichita Well No. _____

Lease: GRESS No. 1

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed September 13, 1964

Application for plugging filed September 13, 1964

Application for plugging approved September 13, 1964

Plugging commenced September 14, 1964

Plugging completed September 14, 1964

Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Herman E. Justus, Nickerson, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4370 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Sand, Shale, Red Bed</u>	<u>Surface Casing</u>	<u>-0-</u>	<u>208'</u>	<u>8-5/8"</u>	<u>208'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED HOLE: Filled hole with heavy mud to 205'. Hulls, bridge & plug @ 205' & 25 sx. cement. Filled hole with mud to 40'. Hulls, bridge & plug plus 10 sx. cement. Hole plugged at 3 a.m. 9-14-64. Plugged rathole w/ 2 sx. cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1964
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor SIERRA PETROLEUM CO., INC.

Address 1015 Wichita Plaza Bldg., Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF RUSSELL, ss.

S. P. Hall, Superintendent (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. P. Hall, Supt.

Box 232, Russell, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of September, 1964

My commission expires 10-17-67

Henry Out
Notary Public.

MULL DRILLING COMPANY - Operator

SIERRA PETROLEUM CO., INC. - Contractor

GRESS #1
C NE SE
Sec. 3-32S-12W
Barber County, Kansas

T. D.: 4370'
Elev.: 1489' D.F.
1492' K.B.

Commenced: 9-4-64
Completed: 9-13-64

Casing:

8-5/8" Set at 208'

Cement:

with 200 sx. Common GL-3

FORMATION

Sand & Shale
Red Bed & Shale
Shale & Shells
Salt & Shale
Shale & Shells
Lime & Shale
Lime, Shale & Sand
Lime & Shale
Lime
Lime & Chert

DEPTH

70
600
1140
1222
1585
3540
3725
3940
4235
4370

RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1964
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

S. P. Hall
Superintendent

Subscribed and sworn to before me this 17th day of September, 1964.

Leroy Dutz
Notary Public

My commission expires: 10-17-67