


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

BARBER County. Sec 2 Twp. 32S Rge. 12 (E) (West)
Location as "NE/CNW/SW" or footage from lines NE NW SE
Lease Owner E. H. Adair, et al.
Lease Name WRIGHT 1 - B Well No. _____
Office Address 1019 E. Second Street, Wichita 7, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) a Dry-hole.
Date well completed 2-17 19 57
Application for plugging filed 2-17 19 57
Application for plugging approved 2-17 19 57
Plugging commenced 2-17 19 57
Plugging completed 2-17 19 57
Reason for abandonment of well or producing formation a dry-hole.

If a producing well is abandoned, date of last production --- 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Pratt, Kansas,
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4355 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
(Copy of driller's log attached hereto).						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug at 225 ft. with 20 sacks of cement on plug and 1-1/2 gallons of hulls in front off plug. Filled hole with mud to 35 ft. in surface pipe put 10 sacks of cement on top plug at 35 feet.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor E. H. Adair Oil Company
Address 1019 East Second Street, Wichita 7, Kansas.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
K. W. Johnson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
1019 E. Second St., Wichita 7, Ks. K. W. Johnson.
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of February, 19 57

My commission expires Sept. 15, 1957.

RECEIVED
STATE CORPORATION COMMISSION
MAY 3-5-57
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 2 T 32 R 12W
BOOK PAGE 142 LINE 7

Hill Notary Public.

E. H. Adair Oil Company
1019 East Second Street
Wichita 7, Kansas.

E. H. Adair Oil Company
No. 1 Wright "B"
NE NW SE of
Sec. 2-Twp. 32S. R. 12 W.
Barber County, Kansas.

Elevation: 1530 K.B.

Comm.: 2-3-57
Comp.: 2-17-57
Contractor:
E.H. Adair, Rig No. 1.
8-5/8 @ 242 ft. w/200 sax.

Pro. D. & A.

Figures indicate bottoms of Formations

Shale & redbeds to	742	Lime	to	3902
Shale	1423	Lime, sl. porous		3910
Shale & lime	1986	Lime		3920
Lime	2100	Shale		3923
Lime & shale	3291	Lime		3963
Shale	3336	Shale		3966
Shaley lime	3377	Lime		3996
Sand & shale	3492	Shale		4000
Shaley lime	3521	Lime, Cherty		4012
Black shale	3526	Lime		4023
Shaley lime	3540	Lime, shaley		4065
Black shale	3545	Shale		4068
Lime	3547	Lime, sl. shaley		4103
Shaley sand	3567	Black shale		4106
Lime	3609	Lime, sl. shaley		4139
Sandy lime	3676	Shale, black		4143
Shale, limey & sandy	3727	Lime		4160
Lime	3730	Shale		4167
Shale	3735	Lime		4195
Lime	3795	Shale		4207
Shale	3797	Lime		4221
Lime, sl. porous	3823	Shale		4229
Shale	3825	Lime		4254
Lime	3856	Shale		4262
Shale	3858	Lime		4272
Lime, porous	3875	Shale		4279
Shale	3882	Lime		4289
		Shaley Chert		4293
		Chert		4355

Certified correct:

K. W. Johnson
K. W. Johnson - Geologist.

RECEIVED
CORPORATION COMMISSION
MAR 5 - 1957
3-5-57
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 2 T 32 R 12W
BOOK PAGE 142 LINE 7