

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

-00-01

API NUMBER 15-077-21,119-A

LEASE NAME Rector

WELL NUMBER 1-8

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 8 TWP. 32 RGE. 8 ~~(E)~~ or (W)

COUNTY Harper

Date Well Completed         

Plugging Commenced 1-18-91

Plugging Completed 11:45 AM

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Fairchild Exploration

ADDRESS Rt. #3, Kingman, Kansas 67068

PHONE#(316) 532-3047 OPERATORS LICENSE NO. 7533

Character of Well gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-18-91 (date)

by Steve Van Giesen (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached?         

Producing Formation          Depth to Top 4412 Bottom 4418 T.D. 3500

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	260	--
				4 1/2	4499	2611.95'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom: Pump 30 sks common w 3% cc to 4300'. Top: Spot 25 sks @ 1500' spot 25 sks @ 900' circulate 125 sks from 300 to surface (60/40 w/4% gel)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 768, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Fairchild Exploration

STATE OF Kansas COUNTY OF Barton, ss.


*1-25-91*  
*Jan 25 1991*

Gary G. Burke

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Gary G. Burke Pres

(Address) Box 768, Great Bend, Kansas 67530



AND SWORN TO before me this 23 day of January, 1991

Lovella S. Muller  
Notary Public

My Commission Expires: 1-13-94