

WELL PLUGGING RECORD


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Harper

County. Sec. 8 Twp. 32 Rge. 8 (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE NE
Lease Owner Mull Drilling Co., Inc.
Lease Name Hadsall Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6-22 19 59
Application for plugging filed 9-8 19 59
Application for plugging approved 19 59
Plugging commenced 9-11 19 59
Plugging completed 9-14 19 59
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampl
Producing formation Miss. Depth to top 4348 Bottom Total Depth of Well 4376 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 200 | |
| | | | | 5 1/2 | 4376 | 3463 |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sand from 4366 to 4320
5 sacks cement
Mud to 190' Rock bridge to 180'
20 sacks cement
Mud to 35' Rock bridge to 25'
10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

SEP 18 1959

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Wilson Inc. (If additional description is necessary, use BACK of this sheet)
Address Stafford, Kansas License # 375

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
D. G. Omstock (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *D. G. Omstock*
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of September, 19 59
Ethel Zimmerman
Ethel Zimmerman Notary Public.

My commission expires January 28, 1961

PLUGGING
File Sec. 8 T32 R8W
Book Page 2 l.f.c. 40

RECEIVED
STATE CORPORATION COMMISSION

SEP 11 1959

CONSERVATION DIVISION
Wichita, Kansas

ROTARY DRILLERS LOG

COMPANY: Mull Drilling Co., Inc. Et Al
Wichita, Kansas

ROTARY DRILLING COMMENCED: 5/28/59

CONTRACTOR: Mull Drilling Co., Inc.
Wichita, Kansas

ROTARY DRILLING COMPLETED: 6/11/59

CASING RECORD: Set 8 5/8" @ 200' cmt/150
sax cmt.
Set 5 1/2" @ 4375' cmt/35 sax
cmt., 65 sax posmix & 30 gal IA-2

LOCATION: HADSALL #1
SE SE NE 8-32S-8W
Harper County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Bushing)

| | |
|-------|------------------------|
| 600' | Red Bed |
| 1260' | Shale & Shells |
| 1720' | Lime & Shale |
| 1960' | Lime |
| 3567' | Lime & Shale |
| 3744' | Sandy Lime & Shale |
| 3882' | Lime w/Shale |
| 4088' | Lime |
| 4338' | Lime w/Shale |
| 4339' | Lime |
| 4375' | Mississippi Chert T.D. |

RECEIVED
STATE CORPORATION COMMISSION

SEP 11 1959

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

MULL DRILLING COMPANY, INC.

Joseph B. Brungardt, Jr.
Joseph B. Brungardt, Jr., Asst. Treas.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 17th day of June, 1959.



Madge N. Miller
Madge N. Miller, Notary Public

PLUGGING

File Sec. 8 T 32 R 8W
Book Page 2 Line 40

My Commission Expires: February 24, 1960