


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas



Locate well correctly on above
Section Plat

HARPER County. Sec. 8 Twp. 32S Rge. 8W (E) (W)
Location as "NE/CNW%SW%" or footage from lines C-SW-SE
Lease Owner DORSET COMPANY
Lease Name BAKER Well No. 1
Office Address 610 NATL. BANK OF TULSA BLDG. TULSA
Character of Well (completed as Oil, Gas or Dry Hole) DRY
Date well completed 10/21/1966
Application for plugging filed 2/1/1967
Application for plugging approved 2/2/1967
Plugging commenced 2/3/1967
Plugging completed 2/6/1967
Reason for abandonment of well or producing formation DRY

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well A. V. ELVING
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4410 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	231'	NONE
				5 1/2"	4384'	3540'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

SAND & CEMENT FROM 4410' TO 4380'
MUD TO 231'
BRIDGE AT 231'
ROCK TO 215'
35 SACK CEMENT TO SURFACE

RECEIVED
STATE CORPORATION COMMISSION

FEB 14 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor WINFIELD OILFIELD SERVICE INC.
Address P.O. Box 952 WINFIELD KANSAS

STATE OF KANSAS COUNTY OF OK HARPER, ss.
CLEM S. KIER (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clem S. Kier
Box 952 Winfield Kans (Address)

SUBSCRIBED AND SWORN TO before me this 13TH day of FEBRUARY, 1967

My commission expires JULY 13, 1970
Anna L. Smith Notary Public.

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

BAKER #1
C SW SE SECTION 8-32S-8W
HARPER COUNTY, KANSAS

COMMENCED: OCTOBER 12, 1966
COMPLETED: OCTOBER 21, 1966

OPERATOR - DORSET COMPANY

DEPTH		FORMATION	REMARKS
FROM	TO		
0	231	RED ROCK	RAN 9 JOINTS OF 8-5/8" CASING, SET @ 231' w/200 SACKS CEMENT.
231	630	RED BED AND SHALE	
630	1280	SHALE	
1280	1400	ANHYDRITE AND SHALE	
1400	1830	LIME AND SHALE	
1830	1940	LIME	
1940	2890	LIME AND SHALE	
2890	3010	SHALE AND SHELLS	
3010	3285	LIME AND SHALE	
3285	3375	SHALE AND SHELLS	
3375	3470	LIME	
3470	3600	LIME, SHALE AND SAND	
3600	3640	LIME AND SHALE	
3640	3785	SHALE AND SAND	
3785	3886	SHALE AND LIME	
3886	4155	LIME	
4155	4390	LIME AND SHALE	
4390	TD		RAN 143 JOINTS OF 5 1/2" CASING, SET @ 4384' w/50 SACKS CEMENT.

36
3506
3785
1487
2298

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE C SW SE SECTION 8-32S-8W, HARPER COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 27TH DAY OF OCTOBER, 1966, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
BARBARA J. LAYTON, NOTARY PUBLIC

My Commission Expires February 1, 1968.

RECEIVED
STATE CORPORATION COMMISSION

FEB 3 1967

CONSERVATION DIVISION
Wichita, Kansas