


15-077-20596-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Harper County, Sec. 17 Twp. 32 Rge. 8W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
660 FSL 1980 FEL  
Lease Owner Texas Oil & Gas Corp.  
Lease Name Robinson Well No. E-1  
Office Address 200 W. Douglas, Suite 300, Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plat

Gas  
Date Well completed 5-25 19 80  
Application for plugging filed 8-19 1980  
Application for plugging approved 8-20 1980  
Plugging commenced 9-25 1980  
Plugging completed 9-27- 1980  
Reason for abandonment of well or producing formation  
Not Productive  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Ownes  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3960  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	202	None
				2 7/8"	3959	2000

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

Halliburton pump in 20 sacks comman cement  
Stop plug 2463

Dialog shoot pipe at 2448 -2245 - 2000  
Pulled 2 1/2 layed down

Halliburton pumped in sacks 8 hull  
25 sacks jell  
125 sacks 50-50 POZ - 3 CC-

RECEIVED  
OCT - 9 1980  
STATE CORPORATION COMMISSION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation

STATE OF Kansas COUNTY OF Barber, ss.  
Elmo R. Margenstern (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) Elmo R. Margenstern  
Medicine Ridge, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of September, 1980

Jessie Hamilton  
Notary Public.

My commission expires April 4, 1982

FILE

DUNBAR DRILLING INC.  
5252 NORTH BROADWAY  
WICHITA, KANSAS 67219  
(316) 832-0501

COMPANY

TEXAS OIL & GAS CORP.

FARM

Robinson "E"

WELL

No. 1

LOCATION

660' FSL & 1980' FEL 17-32S-8W  
Harper County, Kansas

CASING RECORD

8 5/8" @ 202' / 200 sax.  
2 7/8" @ 3959' / 400 sax.

COMMENCED

5/8/80

COMPLETED

5/25/80

DRILLING CONTRACTOR

DUNBAR DRILLING INC.  
5252 NORTH BROADWAY  
WICHITA, KANSAS 67219

-----  
DRILLERS LOG  
-----

0-7	soil
763	shale & red bed
1348	shale
1537	shale with lime streaks
1675	shale & lime
1890	shale with lime streaks
2051	lime & shale
2241	lime & shale
2391	lime & shale
2521	lime & shale
2671	lime & shale
2830	shale & lime
3012	lime & shale
3136	lime & shale with sand
3245	lime & shale
3352	lime with shale streaks
3506	lime & shale
3551	shale with lime streaks
3671	shale & lime
3808	Stalnaker
3939	lime
3960	lime
3960	R. T. D.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 25 1980

CONSERVATION DIVISION  
Wichita, Kansas