

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

HARPER County, Sec. 9 Twp. 32S Rge. 8W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NW NW SW

Lease Owner BARNETT OIL INC.

Lease Name XNXX HOYT Well No. 1

Office Address 1625 Vickers, EST & B Bldg. Wichita 67202

Character of Well (Completed as Oil, Gas or Dry Hole)
GAS

Date Well completed 1-20 1975

Application for plugging filed 9 - 10 1978

Application for plugging approved 9 - 11 1978

Plugging commenced 10 - 18 1978

Plugging completed 10 - 25 1978

Reason for abandonment of well or producing formation
depleted


If a producing well is abandoned, date of last production
March 31 1978

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well BILL OWENS

Producing formation Mississippian Depth to top 4359 Bottom 4361 Total Depth of Well 4361

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	266	NONE
				5 1/2	4359	3555

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

SAND FROM 4361 to 4340. 5 SACKS CEMENT FROM 4340 to 4350. RIPPED AT 3800 - 3700 - 3550. WOOD BRIDGE FROM 280 to 270. ROCK TO 260.
4 yards of ready mix.

RECEIVED
STATE CORPORATION COMMISSION

NOV 6 1978
11-6-78
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form)

Name of Plugging Contractor CLARKE CORPORATION


STATE OF Kansas COUNTY OF Sedgwick, ss.
Dale P. Jewett (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale P. Jewett
1625 Vickers KSB&T Bldg. Wichita, KS
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of November, 1978

My commission expires



Gayle Johnson
Notary Public.

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

WELL #1
 NW-NW-SW Sec 9-32S-8W
 Harper County Kansas

Commenced: 1-9-75

Completed: 1-20-75

OPERATOR: BARNETT OIL INC.

Depth		Formation	Remarks
From	To		
0	515	Redbed	
515	1295	Redbed-Shale	Ran 6 jts of used 8 5/8"
1295	1720	Shale-Shells	csg set @ 256' Cemented
1720	1875	Lime-Shale	w/215 sks Common 2% gel
1875	2060	Lime	3% CC PD @ 4:20 p.m. 1-9-75
2060	2340	Lime-Shale	
2340	2660	Shale-Lime	
2660	3450	Lime-Shale	
3450	3585	Shale-Lime	
3585	3765	Sand-Shale	
3765	4310	Lime	
4310	4361	Lime-Shale	Ran 141 jts of used 5 1/2"
	4361 TD		Csg set @ 4359' Cemented
			w/100 sks Common salt
			sat PD @ 9:00 p.m. 1-20-75

I, James S. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled NW-NW-SW Sec 9-32S-8W Harper County Kansas to the best of my knowledge and belief.

James S. Sutton II
 JAMES S. SUTTON II

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 28th day of January, 1975, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires: November 29th, 1975



Marjorie Hall
 MARJORIE HALL-NOTARY PUBLIC

RECEIVED
 STATE CORPORATION COMMISSION

SEP 11 1978

CONSERVATION DIVISION
 Wichita, Kansas