

WELL PLUGGING RECORD

15-007-21-136-00-00

10 CS 10-9-13  
 RCE

Give All Information Completely  
 Make Required Affidavit

COUNTY Barber SEC. 16 TWP. 33 RGE. 1  
 Location as in quarters or footage from lines:

|  |  |  |  |
|--|--|--|--|
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |

Lease Owner Eagle Explorations, Inc.  
 Lease Name Schooley Well No. 1  
 Office Address Star Route Pratt, Ks. 67124  
 Character of Well (Completed as Oil, Gas or Dry Hole) Never in prod.  
 Date Well Completed 6-15-81  
 Application for plugging filed October, 1983  
 Plugging commenced Oct. 15, 1983  
 Plugging completed Oct. 16, 1983  
 Reason for abandonment of well or producing formation

Locate Well  
 correctly on above  
 Section Platt.

not economical to produce  
 Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
 Producing formation Mississippi Depth to top 4508 bottom 4512 T.D. 5025  
 Show depth and thickness of all water, oil and gas formations. PB TD 4530

OIL, GAS OR WATER RECORDS

Casing Record

| Formation | Content | From | To   | Size   | Put in | Pulled Out |
|-----------|---------|------|------|--------|--------|------------|
|           |         | 0    | 412  | 8 5/8" | 412    | 0          |
|           |         | 0    | 5027 | 4 1/2" | 5027   | 4180'      |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from 4508 feet to 12 feet for each plug set.

Squeezed off perfs. with 35 sx. common cement, 2% gel, 3% calcium chloride.  
Max. pumped 1000 psi. Shut in 600 psi., stopped plug at 4450'. Pulled 4180' 4 1/2" casing,  
pumped 3 hulls, 20 gel, 50 cement, 10 gel, 1 hull, released plug and pumped 125 sx.  
cement, max. pumped 900 psi., shut in 500 psi. Job completed at 5:45 PM by Sun  
Cementing.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pratt Well Service, Inc.

STATE OF Kansas COUNTY OF Pratt, ss.

Judy Berry (employee of owner) or ~~(owner/agent)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Judy Berry  
 Box 847 Pratt, Ks. 67124  
 (Address)

SUBSCRIBED AND SWORN TO before me this 21st day of Nov., 19 83

My Commission expires: 9/10/86

Charlene M. Dudgey  
 Notary Public.  
 NOV 28 1983  
 11-28-1983  
 CONSERVATION DIVISION  
 Wichita, Kansas