

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-21,987-0000

LEASE NAME Ricke

WELL NUMBER T-4

3960 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 4 TWP. 32 RGE. 11 (~~X~~ or (W))

COUNTY Barber

Date Well Completed 1-19-85

Plugging Commenced 1-20-85

Plugging Completed 1-20-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Texas Energies, Inc.

ADDRESS P. O. Box 947 Pratt, Kansas 67124

PHONE#(316) 672-7581 OPERATORS LICENSE NO. 5087

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4450'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Well was plugged with 115 sxs 60/40 poz, 2% gel, 3% cc as follows: 660'-80 sxs; 40'-10 sxs with solid bridge; mousehole-10 sxs; rathole-15 sxs. Job by Sun Cementing, ticket #204589, complete at 9:30 p.m. on January 20, 1985.


(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wheatstate Oilfield Services, Inc. License No. 5149

Address P. O. Box 329, Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Pratt, ss.

James Easter (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.
STATE CORPORATION COMMISSION



(Signature) James A. Easter

(Address) P. O. Box 329, Pratt, Kansas 67124

SUBSCRIBED AND SWORN TO before me this 6th day of February, 1985
Wichita, Kansas

Mary L. Tjaden
Notary Public

My Commission Expires: 3/22/88



- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

Oilfield Services, Inc.

DRILLER'S WELL LOG

Ricke #1-4
 330'W C NE Sec. 4-32S-11W
 Barber County, Kansas
 Commenced: 1-10-85
 Completed: 1-20-85
 API #15-007-21,987
 Operator: Texas Energies, Inc.

Depth		Formation	Remarks
From	To		
0	377	Red Bed	Ran 8 joints (337') new, 23#, 8 5/8" surface casing. Set at 352' with 200 sxs Class A, 2% gel, 3% cc. Job by Sun Cementing, ticket #206506. Cement did circulate. Plug down at 3 a.m. on January 11, 1985.
377	1035	Red Bed, Shale	
1035	4450	Lime, Shale T.D.	

RTD 4450'.

Plugged well with 115 sxs 60/40 poz, 2% gel, 3% cc as follows: 660'-80 sxs 40'-10 sxs with solid bridge; mouse-hole-10 sxs; rathole-15 sxs. Job by Sun Cementing, ticket #204589. Complete at 9:30 p.m. on January 20, 1985. State Plugger was out of the Dodge City, Kansas office.

STATE OF KANSAS)
) ss
 COUNTY OF PRATT)

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

Arnie Little
 ARNIE LITTLE, VICE-PRESIDENT

Mary L. Tjaden
 NOTARY PUBLIC



My Commission Expires:

3/22/88

RECEIVED
 STATE CORPORATION COMMISSION

FEB 07 1985
 2-7-85
 CONSERVATION DIVISION
 Wichita, Kansas