

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

0			

Locate well correctly on above
Section Plat

Barber

County. Sec. 6 Twp. 32 Rge. (E) 11 (W)

Location as "NE/CNW/SW" or footage from lines NW NE Nw

Lease Owner Lario Oil & Gas Company

Lease Name John Regnier

Well No. 1

Office Address 301 S. Market, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed January 25, 1960

Application for plugging filed (verbal) January 25, 1960

Application for plugging approved January 25, 1960

Plugging commenced January 26, 1960

Plugging completed January 26, 1960

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill LeKamp

Producing formation Depth to top Bottom Total Depth of Well 4647 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	227.57	
					Set @	238'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud from total depth to 210'. Set plug at 210' with 1/3 sack hulls and 20 sacks cement. Filled with mud to 35'. Set plug at 35' with 10 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JAN 28 1960
1-28-60
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Prime Drilling Company
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

H. E. Miller

(employee of owner) or (owner or operator)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

301 S. Market, Wichita 2, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of January, 1960

Frances Leake

Notary Public.

My commission expires July 21, 1962



LARIO OIL & GAS COMPANY
 John Regnier No. 1
 NW NE NW Sec. 6-32S-11W
 Barber County, Kansas

Drilling Commenced: January 8, 1960
 Drilling Completed: January 26, 1960
 Drilling Contractor: Prime Drilling Company
 Total Depth - 4647'
 Initial Potential: Dry and Abandoned

CASING RECORD:

8 5/8" 227.57 Set @ 238'
 Cem. w/ 200 sacks

<u>Formation</u>	<u>Depth</u>
Sand	20
Red bed	760
Shale	1270
Anhydrite	1315
Shale & shells	1550
Lime & shale	2500
Shale & lime	2700
Lime & shale	2980
Lime	3200
Lime & shale	3345
Lime	3357
Lime & sand	3475
Lime & shale	3548
Lime, sand & shale	3565
Sand & shale	3696
Lime	4280
Cherty lime	4321
Lime	4347
Lime, shale & chert	4377
Lime & chert	4399
Lime	4440
Lime & shale	4485
Shale & lime	4509
Lime	4623
Sand	4647

GEOLOGICAL TOPS - K.B. MEASUREMENTS

Elevation	1502 R.B.
Elgin Sandstone Zone	3335 (-1833)
Heebner	3467 (-1965)
Douglas Sand Zone	3487 (-1985)
Clean Douglas Sand	3560 (-2058)
Lansing	3695 (-2193)
Mississippi Chat	4254 (-2752)
Mississippi Lime	4317 (-2815)
Kinderhook	4387 (-2885)
Viola	4512 (-3010)
Simpson	4603 (-3101)
Simpson Sand	4614 (-3112)
Rotary Total Depth	4647
Schlumberger Total Depth	4647