


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

BARBER County. Sec. 27 Twp. 31 SRge. 12 WE/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C - SW NE

Lease Owner GRAVES DRILLING COMPANY
Lease Name DURELL Well No. 1
Office Address 910 Union Center, Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry



Locate well correctly on above
Section Plat

Date Well completed 4-22 1978
Application for plugging filed 8-8 1978
Application for plugging approved 8-11 1978
Plugging commenced 9-14 1978
Plugging completed 19

Reason for abandonment of well or producing formation
DRY
If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well BILL OWENS
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4345
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	206	NONE
				4 1/2	4350	3523

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

SAND - FROM - 4350 to 4300. 4 sacks cement - 4300 to 4270

WOOD AT 340' - ROCK TO 310.

4 YARDS READY MIX.

RECEIVED
STATE CORPORATION COMMISSION

OCT 3 1978

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor CLARKE CORPORATION

STATE OF Kansas COUNTY OF Barber, ss.
Elmo Margenstern (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Elmo Margenstern
Medicine Lodge, Mo.
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of September, 1978

My commission expires April 4, 1982

Jessie Hamilton
Notary Public.

R O T A R Y D R I L L E R S ' L O G

CONTRACTOR: Graves Drilling Co., Inc.
910 Union Center
Wichita, Kansas 67202

DRILLING COMMENCED: April 14, 1978

OPERATOR: Graves Drilling Co., Inc.
910 Union Center
Wichita, Kansas 67202

DRILLING COMPLETED: April 22, 1978

CASING RECORD: 5 Jts. 206' 8 5/8 used
cemented with 185 sacks

113 Jts. 4350' 4 1/2" new
cemented with 75 sacks

LOCATION: Durell No. 1
C SW NE
Section 27-31S-12W
Barber County, Kansas

0 - 206 Red Bed
206 - 400 Red Bed & Shale
400 - 1793 Shale & Lime
1793 - 2697 Lime & Shale
2697 - 3183 Shale & Lime
3183 - 3660 Lime & Shale
3660 - 3737 Sand
3737 - 4228 Lime & Shale
4228 - 4345 Lime

4345 Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION
AUG 08 1978
CONSERVATION DIVISION
Wichita, Kansas


I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By Phil Graves
President

STATE OF KANSAS)
) ss.
SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 3rd day of May, 1978.



Betty Brandt
Betty Brandt Notary Public

My commission expires:
May 9, 1979

*copies sent to: Kansas Geological Society
Kansas Geological Survey
State Corporation Commission*