


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barber County. Sec. 13 Twp. 31S Rge. 13W (E) (W)
Location as "NE/CNW&SW&" or footage from lines 330 - S & 2310 * W
Lease Owner Continental Oil Company
Lease Name Aaron Smith Well No. 1
Office Address Box 30 Lyons, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed _____ 19____
Application for plugging filed June 19, 1963 19____
Application for plugging approved June 23, 1963 19____
Plugging commenced June 25, 1963 19____
Plugging completed June 27, 1963 19____
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. V. Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well PB4274 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13 3/8	260	None
				5 1/2	None	2450

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in. Rigged up. Cleaned out cellar. Pushed plug to 3550' and 25' of sand. Dumped 5 sacks of cement. Working pipe. Welded on 5 1/2" collar.
Working pipe. Shot at 2600' - 2500' - 2430'. Pulling pipe.
Plugging with mud to 265'. Build 10' rock bridge. Dumped 35 sacks of cement. Filled hole and rock bridge. Capped well with 20 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL 1 1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28 day of June, 1963

My commission expires May 27, 1964 _____ Notary Public.

INVOICED
DATE 7/1/63
INV. NO. 7223-W

DRILLERS' LOG

Well Owner: Continental Oil Company
Well Name: A. Smith Well No. 1
Commenced: 11/ 8/61
Completed: 12/4/61
Total Depth: 4670'
Casing: 13-3/8" @ 259' cem.
5-1/2" @ 4303' cem.
Contractor: Peel Brothers, Inc.

330' SL; 2310' WL
Sec. 13, Twp. 31S, Rge. 13W
County: Barber, Kansas
Elevation:
Production:

Figures below indicate bottoms of formations:

Surface Clay	0-	40
Red bed		875
Anhydrite		900
Shale & shells		1440
Shale & salt		1575
Shale & lime		3565
Sand		3592
Shale & lime		3705
Lime		4220
Lime & chert		4305
Lime		4330
Shale & lime		4390
Lime		4442
Lime & chert		4467
Lime		4525
Lime & sand		4555
Lime & shale		4588
Lime		4670
Total Depth		4670

This is to certify that the above information is to the best of our knowledge, true and correct.

PEEL BROTHERS, INC.

BY Mendell G. Peel

SUBSCRIBED AND SWORN to before me this 7 day of December, 1961.

My commission expires: April 27, 1964

Luth Brack
Notary Public

*State Corp; Comm.
Kansas Geological Society
CRW
File

RECEIVED
STATE CORPORATION COMMISSION

JUL 19 1963

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED

Faint, illegible text at the top of the page, possibly a header or address block.

Vertical column of faint, illegible text on the left side of the page.

Faint, illegible text line in the middle of the page.

Handwritten signature



RECEIVED
JUL 1 1961
COMMUNICATIONS DIVISION

