

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 P. O. BOX 17027
 WICHITA, KANSAS 67217

WELL PLUGGING RECORD

Bzrber County. Sec. 34 Twp. 31 Rge. 15 (E) W (W)

Location as "NE/CNW&SW" or footage from lines SW NE SE

Lease Owner Westmore Drilling Co., Inc.

Lease Name Skinner 'D' Well No. 2

Office Address Chapin Bldg. ; Medicine Lodge, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19 _____

Application for plugging filed August 19 74

Application for plugging approved August 19 74


Plugging commenced September 17 19 74

Plugging completed September 24 19 74

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Russell Biberstein

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	315	None
				5 1/2"	4780	3122
RECEIVED STATE CORPORATION COMMISSION NOV 22 1974 CONSERVATION DIVISION Wichita, Kansas						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

September 17, 1974 Plugged off bottom. Dumped sand to 4400'. Mixed and dumped 5 sx of cement.

September 24, 1974 Plugged off top. Set 10' rock bridge at 240'. Filled 8 5/8" surface casing from 240' to base of cellar with 3000 lb. P.S.I. ready-mix concrete.

Name of Plugging Contractor RUSS CASING PULLING, INC. (If additional description is necessary, use BACK of this sheet)

Address P. O. Box 1082 ; Great Bend, Kansas 67530

STATE OF KANSAS COUNTY OF BARBER, ss.

R. O. Thompson (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. WESTMORE DRILLING COMPANY, INC.

(Signature) R. O. Thompson

Chapin Building, Medicine Lodge, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of November, 19 74

My commission expires 2-22-76

Imogene Fitzsimmons
 Imogene Fitzsimmons Notary Public.

SKINNER "D" NO. 2

Casing Record: Company: Aylward Drilling Company et al Location: SW NE SE 34-31-15W
 8 5/8" - 211' Contractor: Aylward Drilling Company Barber County
 5 1/2" - 4810' Commenced: August 28, 1957 Elevation: 1914 RB
 Completed: Sept. 14, 1957

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Red Rock & Gyp	0	400	Set 8 5/8" surface pipe @ 211' w/160 sacks cement
Sand	400	450	
Red Bed & Shells	450	955	Geological Tops:
Red Bed	955	1018	
Red Bed & Shells	1018	1115	Heebner Shale 3968
Anhydrite	1115	1160	Base/Oread 4011
Shale & Shells	1160	1365	Douglas Sand 4029
Salt	1365	1425	Lansing 4150
Shale & Shells	1425	1907	Base/Kansas City 4573
Lime & Shale	1907	2180	Mississippian 4670
Lime	2180	2260	Kinderhook Shale 4760
Lime & Shale	2260	2700	Viola 4891
Shale & Lime	2700	2905	Simpson 5014
Lime & Shale	2905	3075	RTD 5037
Shale & Lime	3075	3720	DST 4672-4730 Open 1 hr. Gas to surf. in 2 1/2 min., gauged 1,450 MCFG/50 min. dec. to 1,140 MCFG/1 hr. Rec. 150' GCM FP 330#-230#. 1BHP 1630#/25 min. - FBHP 1190#/20 min.
Lime & Shale	3720	3928	
Shale	3928	4001	5 1/2" casing @ 4810' w/100 sacks cement.
Shale & Lime	4001	4029	
Sand & Sandy Shale	4029	4083	
Sandy Shale & Lime	4083	4172	
Lime	4172	4571	
Lime & Shale	4571	4665	
Lime	4665	4699	
Chert	4699	4730	
Lime & Shale	4730	4918	
Cherty Lime	4918	5037 T.D.	

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 30 1974
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul W. Hesse

Subscribed and sworn to before me this 25th day of October, 1957

Duane Jessup
 DUANE JESSUP Notary Public

My Commission expires: December 11, 1957