


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Barber County. Sec. 33 Twp. 31S Rge. 15 (E) (W)
Location as "NE/CNW%SW%" or footage from lines C-SE 1/4
Lease Owner Aylward Drilling Company
Lease Name D.W. Skinner Well No. 1-A
Office Address _____
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed December 30 1952
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced December 19 1969
Plugging completed December 24 1969
Reason for abandonment of well or producing formation _____
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Herman Justus
Producing formation Mississippi Depth to top 4741 Bottom 4763 Total Depth of Well 4763 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	295	None
				5 1/2	4741	3750

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped chat From 4763 to 4735
Dumped cement with dump bailer - 5 sacks From 4735 to 4700
Ripped pipe at 4000 - 3900 and 3750
Built wood bridge at 240. Then rock from 240 to 230. Dumped in 4 1/2 yards of Ready Mix cement from 230 to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
JAN 21 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Oilfield Service, Inc.
Address Box 187, Medicine Lodge, Kansas 67104

STATE OF KANSAS, COUNTY OF BARBER, ss.
LLOYD L. CLARK (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lloyd L. Clarke

(Address) _____

SUBSCRIBED AND SWORN to before me this 3rd day of January, 1970

Jessie Hamilton
Notary Public.



D. W. SKINNER #1A

Casing Record:	COMPANY: Aylward Drilling Company et al	Location:
8-5/8" 295'	CONTRACTOR: Aylward Drilling Company	Center SE/4
5-1/2" 4741'	COMMENCED: December 11, 1952	Section 33-31S-15W
	COMPLETED: December 30, 1952	Barber County, Kansas
		Elevation: 1918'

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface soil	0	133	
Redbed & Shale	133	485	Set 295' 8-5/8" with 205 sacks cement.
Redbed	485	500	
Redbed & Shale	500	800	
Shale & Lime	800	955	
Shale & Lime	955	1034	
Lime & Anhydrite	1034	1080	
Ruff	1080	1090	
Blue Shale & Anhydrite	1090	1115	
Hard & Ruff	1115	1165	
Arbuckle & Shale	1165	1274	
Soft Lime & Shale	1274	1400	
Hard Lime	1400	1485	
Shale & Shells	1485	1625	
Shale	1625	1700	
Shale & Shells	1700	1895	
Lime	1895	2510	
Fort Riley Lime	2510	2555	
Lime & Shale	2555	2570	
Shale	2570	2612	
Lime	2612	2725	
Broken Lime	2725	2785	
Lime & Shale	2785	3000	
Broken Lime	3000	3135	
Shale & Lime	3135	3200	
Sandy Lime & Shale	3200	3375	
Broken Lime	3375	3495	
Shale	3495	3585	
Shale & Lime	3585	3615	
Broken Lime	3615	3770	
Lime & Shale	3770	3875	
Shale	3875	3900	
Sand Shale & Broken Lime	3900	4000	
Lime & Shale	4000	4065	
Broken Lime & Shale	4065	4105	
Lime	4105	4155	
Shale & Lime	4155	4215	
Broken Lime	4215	4275	
Lime	4275	4540	
Sharp Lime	4540	4575	
Lime	4575	4640	
Lime & Shale	4640	4695	
Lime & Shale Streaks	4695	4725	
Lime & Chert	4725	4763	Set 4741' 5-1/2" Casing and cemented with 200 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 1 1960
CONSERVATION DIVISION
Wichita, Kansas

Tops:

Heebner	3998'	
Lansing	4177'	
Base Kansas City	4580'	
Conglomerate	4725-41'	Drill Stem Test 4723-63. Tool open ten minutes, gas in one minute, recovered eight million cubic feet.
Mississippi	4741	B.H.P. 1600 Lbs. Pay from 4741-60. R.T.D. 4763

I certify that this is a true and correct copy of the above log to the best of my knowledge.

AJ Skalsky
AJ Skalsky

Subscribed and sworn to before me this 6th day of January, 1953.

Florence Cooper
Notary Public

My Commission Expires: July 16, 1956.