


Ⓟ

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Barber County, Sec. 33 Twp. 31 Rge. 15W (E) (W)
Location as "NE/CNW&SW" or footage from lines SE SE NE
Lease Owner ~~XXXXXXXXXXXX~~ Westmore Drilling Company, Inc.
Lease Name Skinner #1 Well No.
Office Address Medicine Ledge, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 5/31/71 19
Plugging completed 6/4/71 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein
Producing formation Depth to top Bottom Total Depth of Well 5167 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				12"	200	none
				10"	1146'	none
				7"	4825'	2485'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 4825', ran sand to 3500' and ran 6 sacks of cement. Loaded hole with 4 leads water. Shot pipe at 2776', 2682', 2592', 2496', pulled 83 joints of 7" casing. Set rock bridge at 250' and ran 6 yards concrete. Tallied pipe.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JUN 16 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Noel Knight*
CHASE, KANSAS
(Address)

MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

9th day of June, 1971
Margaret Melcher
Notary Public.

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


COPY

Company - CONTINENTAL OIL CO.
Farm - D.W. Skinner No. 1.

SEC. 33 T. 31 R. 15 W
SEc NE
330' N & 300' W of E $\frac{1}{4}$ Cor.

Total Depth. 5167
Comm. 11-19-45 Comp. 3-27-46
Shot or Treated.
Contractor.
Issued. 7-6-46

County: Barber
KANSAS



CASING:
16" 200' 7" 4825'
10 3/4" 1146' 2 7/8" 4768'

Elevati. n. 1922

Production. Open Flow 2,500,000
cu.ft.

Figures Indicate Bottom of Formations.

sand, shale & red rocks	220
shale, shells & red bed	460
red bed & shells	835
shale, shells, red bed	900
shale & shells	1135
anhydrite	1137
shale & shells	2025
lime & shale	2115
lime	2530
shale & shells	2415
lime brkn	2620
lime sdy	2745
lime	2805
lime sdy	3030
lime & shale	3220
lime brkn	3390
lime	3595
lime & shale	3707
lime	3750
lime & shale	3795
lime	4435
lime & chert	4485
lime	4636
lime & shale	4655
lime	5035
lime & chert	5060
lime	5088
shale & lime	5115
shale sdy	5145
lime	5167
Total Depth	

Tops:
Douglas sand 4050
Miss. Lime 4695
Arbuckle lime 5143

RECEIVED
STATE CORPORATION COMMISSION
DEC 9 - 1970
CONSERVATION DIVISION
Wichita, Kansas

1917

RECEIVED
NOV 14 1970