


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Barber County, Sec. 33 Twp. 31 Rge. 15 (E) W (W)  
Location as "NE/CNW&SW" or footage from lines NE/4  
Lease Owner Aylward Drilling Co.  
Lease Name Skinner "B" #1 Well No. \_\_\_\_\_  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 9-2-58 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 9-6-58 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Lac Kamp  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4800' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	565'	none
				5-1/2"	4702'	4313'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked the hole to 4800' and found it open.  
Set bridging plug at 4600' and dumped 2 sacks of cement. Pulled 80 jts of casing and pumped in 17 sacks of gel mud, lost circulation. Pulled 5 more jts of pipe and pumped in 11 sacks of gel mud, still no circulation. Pulled rest of casing, cleared hole and checked fluid to 350'. Mudded the hole to 300', set rock bridge to 290' and dumped 20 sacks of cement. Mudded the hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETED

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor WEST SUPPLY CO., INC.  
Address Chase, Kansas

DEC 29 1958  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss. I, Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of September, 19 58

9-27-58

Thomas V. Duggin  
Notary Public.

My commission expires \_\_\_\_\_

PLUGGING  
FILE SEC 33 T 31 R.15W  
BOOK PAGE 126 LINE 15

SKINNER "B" #1

Casing Record:

8 5/8" - 565'  
5 1/2" - 4702'

Company: Aylward Drilling Company  
Contractor: Aylward Drilling Company

Commenced: February 21, 1956  
Completed: March 12, 1956

Location: NW SE NW  
Sec. 33-31-15W  
Barber County  
Kansas

Elevation: 1894 D.F.

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Red Rock	0	106	8 5/8" casing set @ 565' with 400 cu. ft. Pozmix
Red Rock and sand	106	395	
Dakota sand	395	494	
Red rock and gyp	494	815	
Anhydrite	815	830	
Shale and shells	830	1140	
Gray shale with lime streaks	1140	1400	Geological Tops:
Lime and shale	1400	1790	
Lime	1790	1855	Heebner 3990 - 2096
Lime and shale	1855	2015	Base Oread 4026 - 2132
Lime	2015	2050	Douglas Sand 4067 - 2173
Lime and shale	2050	2325	Brown Lime 4140 - 2246
Lime	2325	2405	Lansing 4644 - 2750
Lime and shale	2405	2460	Conglomerate 4698 - 2804
Lime	2460	2475	
Lime, broken	2475	2530	
Lime and shale	2530	3105	
Lime	3105	3130	
Shale and lime	3130	3285	
Broken lime	3285	3360	
Sandy lime	3360	3485	
Lime and shale	3485	3563	
Sandy lime	3563	3592	
Lime	3592	3880	
Sandy lime	3880	3973	
Lime and shale	3973	4059	
Lime	4059	4101 <42'	
Sandy lime	4101	4145	
Lime and shale	4145	4195	
Lime	4195	4610	
Lime and shale	4610	4665	
Lime	4665	4700	Set 5 1/2" casing @ 4702 w/50 sx cement
Lime and chert	4700	4704 T.D.	

- 2910

I certify that this is a true and correct copy of the above log to the best of my knowledge.

*Paul W. Hesse*  
Paul W. Hesse

Subscribed and sworn to before me this 15th day of March, 1956

**RECEIVED**  
STATE CORPORATION COMMISSION  
*Duane Jessup*  
Duane Jessup Notary Public  
MAY 21 1956  
10-21-56

My commission expires December 11, 1957

**PLUGGING**  
FILE SEC 33T31 R 15W  
BOOK PAGE 126 LINE 15

CONSERVATION DIVISION  
Wichita, Kansas