


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County. Sec. 27 Twp. 32S Rge. 12 xx/W
Location as "NE/CNW/SW" or footage from lines
150' SW of C SW SE

Lease Owner American Petroleum Co., Inc.
Lease Name Ash No. A-1 Well No. A-1
Office Address 400 N. Woodlawn, Wichita, Ks. 67208
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

dry hole
Date Well completed 8-29 1977
Application for plugging filed 8-29 1977
Application for plugging approved 8-29 1977
Plugging commenced 8-29 1977
Plugging completed 8-29 1977

Reason for abandonment of well or producing formation _____
no commercial quantities of oil or gas encountered
If a producing well is abandoned, date of last production
_____ 19__

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Owens
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4817
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
surface hole	shale	surface	264	8-5/8	254	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Fluid to 400, plug, 40 sx
Fluid to 250, plug, 20 sx
Fluid to 40', plug, 12 sx
3 sx in rat hole

RECEIVED
STATE CORPORATION COMMISSION

SEP 01 1977

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor DNB DRILLING, INC.
515 R. H. Garvey Building
Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Kansas, ss.
Ella Priess (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Ella Priess
Suite 515, R.H. Garvey Bldg., Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of August, 19 77

My commission expires April 30, 1979

Dorothy L. Schmidt
Dorothy L. Schmidt
Notary Public.

DOROTHY L. SCHMIDT
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. April 30, 1979

DRILLERS' LOG

AMERICAN PETROLEUM CO., INC.

No. A-1 Ash

150' SW of C SW SE

Barber County, Kansas

Commenced: 8-19-77

Completed: 8-31-77

Surface Casing: 254' of 8-5/8"

cmtd w/200 sx common, 2% gel, 3% cc
8-19-77

FORMATION

DEPTH

Surface Hole	0 - 264
Shale	264 - 922
Shale & Shells	922 - 1600
Shale & Lime	1600 - 1870
Shale	1870 - 2081
Shale & Lime	2081 - 2295
Lime & Shale	2295 - 3670
Lime	3670 - 4775
Shale	4775 - 4780
Lime	4780 - 4817 RTD

RECEIVED
STATE CORPORATION COMMISSION

SEP 01 1977

CONSERVATION DIVISION
Wichita, Kansas

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

Ella Priess

Ella Priess

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 31st day of August, 1977.

Dorothy L. Schmidt

Dorothy L. Schmidt, Notary Public