

15-1165-00148-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

OR  
FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.



Locate well correctly on above  
Section Plat

Rush County, Sec. 21 Twp. 19 Rge. 14 (E) (W)  
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. 330'-330'  
Lease Owner. Campbell + Buhler  
Lease Name. Hageman  
Office Address. 403 Union Chat - Bank Bldg Wichita  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed. 5-7 19.50  
Application for plugging filed. 5-8 19.50  
Application for plugging approved. 5-8 19.50  
Plugging commenced. 5-8 19.50  
Plugging completed. 5-16 19.50  
Reason for abandonment of well or producing formation. Dry hole

If a producing well is abandoned, date of last production. — 19. —  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well. C. N. Blough  
Producing formation. Arbuckle Depth to top. 3795 Bottom. 3890 Total Depth of Well. 3890 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Dry	3795	3890	8 5/8" 5 1/2"	1150' 3890'	none, 2200'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Band Chat + cement from 3890' to 3775' - 13 sacks cement  
mudded from 3775' to 250' to 220' - 15 sacks cement  
Chat + pop. fudge at 250' - 15 sacks cement  
Mudded 30' - 16 sacks cement to surface

RECEIVED

MAY 28 1950  
5-23-50

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. Campbell + Buhler  
Address. 1415 Jackson St - Great Bank Bldg

STATE OF \_\_\_\_\_, COUNTY OF \_\_\_\_\_, ss. \_\_\_\_\_

\_\_\_\_\_ (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-  
described well as filed and that the same are true and correct. So help me God.

(Signature) *W. Campbell*

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 20<sup>th</sup> day of May, 1950  
*Maile Inadgane*  
Notary Public.

My commission expires Aug 9 - 1953  
PLUGGING 20-300-11-43-10M  
21-19-1950  
6-15

COMPANY: Campbell & Kuhn  
 LEASE: Hagerman # 1  
 COUNTY: Rush 21-19-16W  
 CONTRACTOR: Campbell Drilling Company  
 WELL COMMENCED: 3-29-50  
 WELL COMPLETED: 5-3-50

0-50	post rock & sandy clay
50-90	clay
90-240	shale & shells
240-340	shale & shells
340-460	shale & shells
460-480	sand
480-550	shale
550-660	sand
660-695	sand, gravel & shale
695-1100	red bed
1100-1152	red bed
1152-1160	anhydrite & shells
1160-1175	anhydrite
1175-1340	red bed & clay
1340-1560	shale, shells & salt
1560-1900	shale & shells
1900-1920	lime
1920-1995	lime & shale
1995-2100	sandy lime
2100-2310	lime
2310-2370	lime
2370-2450	lime & shale
2450-2600	shale & lime
2600-2820	shale & lime
2820-3035	shale & lime
3035-3170	shale & lime
3170-3195	lime dark gray
3195-3242	lime
3242-3420	shale & lime
3420-3480	shale & lime
3480-3605	lime
3605-3650	lime
3650-3765	lime
3765-3805	lime
3805-3833	cherty lime
3833-3860	lime
3860-3890	lime

T D

ran 1158' of 8 5/8" casing  
 cemented with 350 sks  
 cement.

elevation 2092' D.F.

Top of Kansas City Lime 3488'

Top of Arbuckle Lime 3795'

Ran 3920' of 5 1/2" casing

Acidized with 500 gallons (Dowell)

**PLUGGING**  
 FILE SEC 21-19-16W  
 BOOK PAGE 6 LINE 15

INDEXED  
 5-23-58  
 MAY 23 1950  
 STATE CORPORATION  
 COMMISSION  
 KANSAS



Perforation:

3rd Zone

3 holes ----- 3825-26'  
12 holes ----- 3817-21'

4th Zone or top zone

12 holes -----3801-3805'  
12 holes -----3797-3801'  
6 holes -----3795-97'

3 holes top of bottom zone ----- 3839-3840'  
3 holes " " " " ----- 3840-41'  
6 holes " " " " ----- 3841-43'  
12 holes " " " " ----- 3843-47'  
12 holes " " " " ----- 3847-51'  
12 holes " " " " ----- 3851-55'  
12 holes " " " " ----- 3855-59'

Bottom Zone dry

3 holes in 2nd zone ----- 3834-35'  
3 holes " " ----- 3835-36'  
3 holes " " ----- 3836-37'  
3 holes " " ----- 3837-38'  
3 holes " " ----- 3838-39'  
3 holes " " ----- 3839-40'

Perforated 12 holes --- 3828-3832'

No Oil or Gas

STATE OF KANSAS )  
COUNTY OF SEDGWICK ) ss

I, the undersigned, being duly sworn, on oath that the above statement and log is a true and correct record and log of the well drilled at the location above mentioned.

CAMPBELL DRILLING CO.

By Nadine Williams

Sworn and subscribed to before me this 19th day of May 1950.

Ruth Passwater  
Notary Public

My comm. Expires:  
4-5-54

RECEIVED  
Corporation Div.  
5-23-50  
MAY 23 1950  
STATE CORPORATION  
COMMISSION  
KANSAS