

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-165-21,583-0000

LEASE NAME Miller

WELL NUMBER 2

990 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 36 TWP. 19 RGE. 16 (E) or (W)

COUNTY Rush

Date Well Completed 07-29-91

Plugging Commenced 07-29-91

Plugging Completed 07-29-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR James R. Isern

ADDRESS 221 S. Broadway, Suite 605 Wichita, KS 67202

PHONE#(316) 267-1331 OPERATORS LICENSE NO. 30382

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-26-91 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? to be filed by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3830

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
						<u>AUG 02 1991</u> <u>8-2-91</u> COMMISSION DIVISION WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 3665' w/50 sacks cement thru drill pipe

Next Plug: @ 1050' w/50 " " " " " 15 sacks in Rat Hole

Next Plug: @ 600' w/40 " " " " "

Top Plug: @ 40' w/10 " " " " "

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: James R. Isern

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson

(Employee of Operator) or ~~Operator~~ of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Leonard Williamson

(Address) P.O. Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 31st day of July, 19 91

Paula Ann Laudick
Notary Public

My Commission Expires: _____



15-165-21583-0000

DRILLER'S WELL LOG

DATE COMMENCED: July 22, 1991
DATE COMPLETED: July 29, 1991

James R. Isern
MILLER #2
NW SE SW
Sec. 36, T19S, R16W
Rush County, Ks.

0 - 102' Surface Soil, Clay, Sand
102 - 398' Shale w/sand streaks
398 - 541' Sand
541 - 1016' Red Bed
1016 - 1036' Anhydrite
1036 - 1066' Red Bed
1066 - 1700' Shale
1700 - 2978' Lime & Shale
2978 - 3317' Lime
3317 - 3346' Shale & Lime
3346 - 3394' Shale
3394 - 3404' Lime & Shale
3404 - 3620' Lime
3620 - 3674' Shale & Lime
3674 - 3830' Dolomite
3830' RTD

ELEVATION: 1988 K.B.

Surface Pipe: Set used
8-5/8", 23# pipe @ 1024'
w/375 sacks 60/40 pozmix
2% gel 3% cc.

AFFIDAVIT

STATE OF KANSAS
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 31st day of July 1991.



Paula Ann Landick
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
8-2-91
AUG 02 1991

CONSENT DIVISION
Wichita, Kansas