

LEASE NAME Wingate

WELL NUMBER 4

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 7 TWP. 31s RGE. 8W (E) or (W)

COUNTY Harper

Date Well Completed

Plugging Commenced 4-18-97

Plugging Completed 4-23-97

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Co.

ADDRESS P. O. Box 21468 Tulsa, OK 74121-1468

PHONE#(918) 491-4314 OPERATORS LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.O. 4405'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	222'	none
				4 1/2	4405'	2400'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet. Each s
Pulled all rods & tubing. Sanded bottom to 4350' & ran 4 sks cement. Shot casing at 2600'.
put on tension overnight. Still not loose. Shot at 2400'. pipe came loose. Pulled to 2425'.
mixed 35 sks cement w/150# hulls. Pulled to 950'. mixed 35 sks cement w/150# hulls. Pulled to
275', pumped 145 sks cement and circulated to surface. Pulled rest of pipe Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. W 529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Co.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)
 above-described well, being first duly sworn on oath, says: That I have knowledge of the fac
 statements, and matters herein contained and the log of the above-described well as filed t
 the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 6th (day of May), 19 97

Irene Herzberg
 Notary Public

My Commission Expires:



DRILLERS LOG

Wingate No. 4

<u>CASING RECORD:</u>	<u>COMPANY:</u>	Drillers Prod. Co., Inc.	<u>DESCRIPTION:</u>
8 5/8" @ 222.20'	<u>CONTRACTOR:</u>	Red Tiger Drilling Co.	C SE SW
w/175 sx cement	<u>COMMENCED:</u>	September 12, 1967	7-31S-8W
4 1/2" @ 4405'	<u>COMPLETED:</u>	September 21, 1967	Harper, Co., K
w/100 sx cement			<u>ELEVATION:</u>
<u>TOTAL DEPTH:</u> 4405'			

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	100	
Shale & Red Bed	100	225	
Shale and Red Bed & Shells	225	1130	
Shale & Shells	1130	1575	
Shale with Lime	1575	1890	
Lime	1890	2030	
Lime & Shale	2030	3170	
Lime	3170	3310	
Lime and Shale	3310	4000	
Lime	4000	4405	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Maxine V. Starr
Maxine V. Starr

Subscribed and sworn to before me this 25th day of September, 1967.

Betty M. Maloney
Notary Public

My Commission Expires:

3-22-71

1967 SEP 25 12:01
KANSAS DISTRICT COURT
9-14-67