

15-077-10067-0000

API NUMBER Spud 12-20-54

LEASE NAME Grabs B

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 7 TWP. 31s RGE. 8W (E) or (W)

COUNTY Harper

Date Well Completed

Plugging Commenced 4-15-97

Plugging Completed 4-17-97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468 Tulsa, OK 74121-1468

PHONE#(918) 491-4314 OPERATORS LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? if not, is well log attached?

Producing Formation Depth to Top Bottom T.O. 4515'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	168'	none
				5 1/2	4501'	2414'

Describe in detail the manner in which the well was plugged, indicating where the plug fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s
Pulled all rods & tubing. Sanded bottom to 4300' & ran 5 sks cement. Shot well @ 3012', not loose. Shot at 2414', pipe came loose. Pulled up to 1400', pumped 35 sks cement. Pulled to 900', pumped 35 sks cement. Pulled to 250', circulated cement to surface with 110 sks. Pulled rest of pipe. Topped off with 20 sks.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mike's Testing & Salvage, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the fac
statements, and matters herein contained and the log of the above-described well as filed t
the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 6th day of May, 1997

Notary Public

My Commission Expires:



DRILLER'S LOG

Republic Natural Gas Co.
 Grabs #1
 SW NW NW 7-31-8
 Harper County, Kansas

<u>TO</u>	<u>FROM</u>	
0	45	Surface Soil - Shale
45	100	Sand
100	169	Shale & Red Rock
169	290	Red Rock & Shale
290	890	Red Rock, Shale & Shells
890	1385	Shale & Shells
1385	1655	Shale & Lime
1655	2165	Lime
2165	2175	Shale
2175	2730	Shale & Shells
2730	3725	Lime & Shale
3725	4393	Lime
4393	4400	Coring
4400	4408 1/2	Core #1
4408 1/2	4453	Core #2
4393	4453	Reaming Core Hole
4453	4459	Coring
4459	4485	Mississippi Lime
4453	4485	Reaming to 7 7/8"
4485	4515	Drilling
	4515	ROTARY TOTAL DEPTH

COMMENCED: 12-20-54
 COMPLETED: 1-6-54

CASING RECORD:

Set 168' of 8 5/8" surface casing with 150 sacks cement.

Set 5 1/2" casing at 4497' with 100 sacks cement.

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Grabs #1 located SW NW NW in section 7-31-8, Harper County, Kansas.

ANSCHUTZ DRILLING CO., INC.

BY: *E. G. Koelling*
 E. G. Koelling

Subscribed and sworn to before me this 10th day of January, 1955.

Charlene Barbour
 Notary Public

My Commission Expires: July 28, 1958.

RECEIVED
 KANSAS CORP COMM
 1-24-55

2 copies to all 1-17-55