


15-077-00953-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Harper County, Sec. 7 Twp. 31 Rge. 8 (E)W (W)
Location as "NE/CNW/SE" or footage from lines 660 FSL 660 FSL SE/4
Lease Owner National Associated Petroleum Company
Lease Name Winegate #1 Well No.
Office Address Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 6/9/69 19
Plugging completed 6/11/69 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Warren
Producing formation Depth to top Bottom Total Depth of Well 4505 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	181	none
				5 1/2	4503	3273'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Ran sand, set 5 sacks of cement. Rigged up on 5 1/2", loaded hole with water, shot pipe at 3285', pulled 103 joints. Set rock bridge at 180' and ran 25 sacks of cement, mud to 40' rock bridge and ran 10 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
7-3-69
JUL 3 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS


STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS

(Address)

Subscribed and sworn to before me this 13th day of June, 1969



My commission expires 2/15/71

Margaret Melcher
Notary Public.

Office Memorandum

From Joe E. McGarrah

Date December 23, 1963

To Forrest H. Lindsay

Subject #1 Wingate

SE SE Sec. 7-31S-8W
Harper County, Kansas

TYPE: Development STATUS: Oil Well

ELEVATIONS: Ground 1663': D. F. 1665': K. B. 1667'

DEPTHS: Driller 4502': Lane Wells 4505'

DATES: M. I. R. T. November 11, 1963: Under surface November 12, 1963:
Pipe set November 24, 1963.

SURFACE CASING: 8 5/8" surface casing set at 181' w/150 sx Hi-Early, 400# CC.

SPECIAL TESTS: Lane Wells: Gamma Ray Neutron: Focused Log.

FORMATION TOPS:

	SAMPLES	LANE WELLS
Lansing	3647	
Kansas City	3916	
B/Kansas City	4362	4362
Miss	4418	4417
Total Depth	4502	4505

Respectfully submitted

Joe E. McGarrah
Joe E. McGarrah *J.E.M.*

JEM:dc

7/8" HOLE
RAN 142 JTS 5 1/2" 14# J-55 SET AT 4503'
CEM w/ 75 SAX REG, 25 SAX LATEX
PD 1:45 PM 11-23-63
PERF 4428-48' w/2 JET/FT

RECEIVED
STATE CORPORATION COMMISSION
5-27-69
MAY 27 1969
CONSERVATION DIVISION
Wichita, Kansas